



The experience **you deserve**

GOLD COAST OFFICE

P 07 5509 6400 Level 2, 26 Marine Parade, Southport Qld 4215 PO Box 3766, Australia Fair, Southport Qld 4215 **BRISBANE OFFICE**

P 07 3607 6332 Level 14, 167 Eagle Street, Brisbane Qld 4000 PO Box 83, Brisbane Qld 4000

admin@burchills.com.au











The experience **you deserve**







2983 Forest Hill Fernvale Road, Lowood

Traffic Impact Assessment Report

Client: Lowood One Pty Ltd

Project No: BE230128

Document No: BE230128-RP-TIA-04

April 2024

Document Control Record

Prepared by:	Adele Packer
Position:	Traffic Engineer
Signed:	Packer
Date:	24/04/2024

Approved by:	Angela Wood
Position:	Principle Traffic Engineer (RPEQ)
Signed:	Alvood.
Date:	24/04/2024

Version No.	Description	Date	Prepared	Approved
00	Draft for Client Review	9/11/2023	AP	AW
01	Draft for Client Review	1/12/2023	AP	AW
02	Issued for DA	8/12/2023	AP	AW
03	Issued for DA	11/12/2023	AP	AW
04	Issued for DA	24/04/2024	AP	AW

Recipients are responsible for eliminating all superseded documents in their possession

Coote Burchills Engineering Pty Ltd ACN: 166 942 365

Level 2, 26 Marine Parade SOUTHPORT QLD 4215 PO Box 3766, Australia Fair SOUTHPORT QLD 4215 Telephone: +61 7 5509 6400

Level 25/215 Adelaide Street BRISBANE QLD 4000 PO Box 83, BRISBANE QLD 4000 Telephone: +61 7 3606 0201

123 Margaret Street TOOWOOMBA QLD 4350 PO Box 1439, TOOWOOMBA QLD 4350 Telephone: +61 7 4580 4970

SUNSHINE COAST | BANGALOW | MORETON BAY | IPSWICH

Email: admin@burchills.com.au RELIANCE, USES and LIMITATIONS

This report is copyright and is to be used only for its intended purpose by the intended recipient, and is not to be copied or used in any other way. The report may be relied upon for its intended purpose within the limits of the following disclaimer.

This study, report and analyses have been based on the information available to Burchills Engineering Solutions at the time of preparation. Burchills Engineering Solutions accepts responsibility for the report and its conclusions to the extent that the information was sufficient and accurate at the time of preparation. Burchills Engineering Solutions does not take responsibility for errors and omissions due to incorrect information not available to Burchills Engineering Solutions at the time of preparation of the study, report or analyses.

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Impact Assessment

— www.burchills.com.au

Page ii

Table of Contents

5	<u> </u>	www.burchills.co	om.au
	7.2	Car Parking Provision	17
	7.1	Car Parking Requirements	
7.	Ca	r Parking Assessment	17
	6.4	Network Delay Impact	14
	6.3	Forest Hill Fernvale Road / Site Access	14
	6.2	Park Street / Prospect Street	13
	6.1	Peregrine Drive / Forest Hill Fernvale Road	12
6.	SIE	DRA Assessment	12
	5.2	.2 Intersection Degree of Saturation (DoS)	11
	5.2	•	
	5.2	Assessment Criteria	
	5.1	Assessment Scenarios	
5.	Tra	ıffic Assessment Criteria	
	4.5	Traffic Distribution	9
	4.4	Traffic Generation	8
	4.3	Traffic Growth	8
	4.2	Background Traffic Volumes	7
	4.1	Study Intersections	7
4.	Tra	ffic Assumptions and Characteristics	7
	3.2	Vehicle Access	6
	3.1	Development Yield	6
3.	Pro	pposed Development	6
	2.4	Active Transport Facilities	
	2.3	Public Transport Facilities	4
	2.2	.3 Park Street	4
	2.2	.2 Williams Street	3
	2.2	.1 Forest Hill Fernvale Road	3
	2.2	Local Road Network	3
	2.1	Land Uses	2
2.	Exi	sting Conditions	2
	1.3	Report constraints	1
	1.2	References	1
	1.1	Project Overview	1
1.	Intr	oduction	1

The experience you deserve

			www.burchills.com.au
Fig	ure 2.3	Williams Street Facing East (left) and West (right)	3
Fig	ure 2.2	Forest Hill Fernvale Road Facing East (left) and West (right)	3
	jures jure 2.1	Subject Site	2
та	NIE Ö.Ö	Intersection Spacing Assessment	21
		Road Capacity Assessment	
		Crash Data on Forest Hill Fernvale Road (2017-2022) Road Width Assessment	
		SISD Assessment at Site Access Intersection	
		Site Access Trips Peak Hours	
		Intersection Delay Impact – Forest Hill Fernvale Road	
		SIDRA Results – Forest Hill Fernvale Road / Site Access	
		SIDRA Results – Park Street / Prospect Street	
		SIDRA Results – Peregrine Drive / Forest Hill Fernvale Road	
		Impact Assessment Scenarios	
		Development Traffic Generation	
Та		Adopted Peak Periods	
9.	Conc	usions	23
_	8.4.3	Swept Path – 9.9m WCV	
	8.4.2	Waste Collection	
	8.4.1	Service Vehicle Requirements	
8		Servicing	
	8.3.4	Active Transport Provisions	
	8.3.3	. •	
		Intersection Spacing	
	8.3.2	Road Capacities	
(8.3.1	Road Widths and Hierarchy	
		nternal Road Network	
	8.2.3	Safety Assessment on Forest Hill Fernvale Road	
	8.2.2	Sight Distance	
•	8.2.1	Turn Warrants Assessment	
		Access Assessment	
8.	_	n Review Overview	
		Suitability of Car Parking	
-	72 (witchility of Car Darking	17

The experience you deserve

Figure 2.4 Park Street Facing North (left) and South (right)	4
Figure 2.5 Existing Public Transport Connections	5
Figure 3.1 Proposed Development Layout	6
Figure 4.1 Study Intersections	7
Figure 6.1 Aerial and SIDRA Layout – Peregrine Drive / Forest Hill Fernvale Road	12
Figure 6.2 Aerial and SIDRA Layout – Park Street / Prospect Street	13
Figure 6.3 Concept Layout and SIDRA Layout – Forest Hill Fernvale Road / Site Access	14
Figure 6.4 Network Delay Impact	15
Figure 8.1 Turn Warrants Qm Traffic Flow Calculation	18
Figure 8.2 Turn Warrant Assessment (10-Year Design Horizon)	19
Figure 8.3 Site Access Intersection Concept Layout	19
Figure 8.4 Sight Lines from Site Access Location Looking East (left) and West (right)	20

Appendices

Appendix A – Site Layout

Appendix B – Traffic Survey

Appendix C - Traffic Flow Diagrams

Appendix D - SIDRA Outputs

Appendix E – Swept Paths

 \geqslant

- www.burchills.com.au



1. Introduction

1.1 Project Overview

Lowood One Pty Ltd have engaged Burchills Engineering Solutions to prepare a Traffic Impact Assessment (TIA) to be submitted to Somerset Regional Council (the 'Council' or 'SRC'). The Application sought is a Preliminary Approval for a Variation Request pursuant to section 50 of the Planning Act 2016 to allow for future staged development of a 358 lot subdivision, including 19 duplex allotments.

The properties included in this Development Application include:

- Lot 56 Forest Hill Fernvale Road, Lowood (Lot 56 on SP 197415); and
- Lot 57 Forest Hill Fernvale Road, Lowood (Lot 57 on SP 197415).

The purpose of this report is to investigate the potential traffic impacts associated with the proposed development, with reference to the latest development approval for the overall development area.

1.2 References

In the course of preparing this report, reference has been made to the following:

- Somerset Regional Council Planning Scheme
- Department of Transport and Main Roads (TMR) Guide to Traffic Impact Assessments, December 2018
- Roads and Maritime Services (RMS) Technical Direction Guide to Traffic Generating Developments, August 2013;
- Queensland Streets, Design Guidelines for Subdivisional Street Works; and
- Other documents as specified.

1.3 Report constraints

Burchills Engineering Solutions has carried out this traffic report that complies with industry standard traffic engineering practices and standards applicable during the assessment in April 2024. The report was based on the available project information and conditions at the time of the assessment. However, Burchills Engineering Solutions cannot be held responsible for any changes to the project planning or road conditions that occur after the report's completion, which may affect the accuracy of the assessment's findings.

Client: Lowood One Pty Ltd
Doc No.: BF230128-RP-TIA-04

Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Impact Assessment



2. Existing Conditions

2.1 Land Uses

The proposed development is situated at 2983 Forest Hill Fernvale Road, Lowood, formally described as Lot 56 & 57 on SP197415. The surrounding land uses are predominantly residential and rural. The site is located within Somerset Regional Council (SRC) local government area and is currently zoned as 'Emerging Community'. The subject site and its surrounding environs is shown in Figure 2.1.




Figure 2.1 Subject Site

The site is currently vacant land.

 \geqslant

www.burchills.com.au

2.2 Local Road Network

A summary of key roads in the vicinity of the site is provided below.

2.2.1 Forest Hill Fernvale Road

Forest Hill Fernvale Road is an arterial road under the jurisdiction of the Department of Transport and Main Roads (DTMR). It is configured as a two-way, two-lane sealed 6.5m wide carriageway.

Forest Hill Fernvale Road is shown in Figure 2.2 below.






Figure 2.2 Forest Hill Fernvale Road Facing East (left) and West (right)

2.2.2 Williams Street

Williams Street is a local road under the jurisdiction of Somerset Regional Council. It is configured as a two-way, two-lane sealed 8m wide carriageway.

Williams Street is shown in Figure 2.3 below.





Figure 2.3 Williams Street Facing East (left) and West (right)

 \geqslant -

www.burchills.com.au



2.2.3 Park Street

Park Street is a sub-arterial road under the jurisdiction of DTMR. It is configured as a two-way, twolane sealed 13m wide carriageway.

Park Street is shown in Figure 2.3 below.





Figure 2.4 Park Street Facing North (left) and South (right)

2.3 Public Transport Facilities

There is a bus stop pair in Lowood town centre, approximately 1.5km walking distance from the subject site. The location of the bus stops is shown in Figure 2.5 below.

www.burchills.com.au



Figure 2.5 Existing Public Transport Connections

The bus stops are serviced by Route 529 which provides connections between Toogoolawah and Ipswich three (3) times per day.

2.4 Active Transport Facilities

A shared path is available on the southern side of Forest Hill Fernvale Road that provides a connection between the residential dwellings to the west of the site and the Lowood town centre.

Lowood One Pty Ltd

www.burchills.com.au

Doc No.: BE230128-RP-TIA-04 Doc Title: Traffic Impact Assessment



3. Proposed Development

3.1 Development Yield

The proposed overall masterplan development comprises a low-density residential subdivision that includes 358 lots (including 19 duplex lots) for a total of 377 dwellings.

A layout of the proposed ultimate masterplan development plan is shown in Figure 3.1 below and can be found at Appendix A.



Figure 3.1 Proposed Development Layout

3.2 Vehicle Access

Vehicle access to the development is proposed via a new access intersection on Forest Hill Fernvale Road. A secondary access is proposed via a connection to Williams Street to the east of the site. A detailed review of the site accesses is included in Section 8.2.

> —

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Impact Assessment



4. Traffic Assumptions and Characteristics

4.1 Study Intersections

The traffic impacts of the proposed development on the surrounding road network have been assessed in accordance with DTMR's Guide to Traffic Impact Assessments (GTIA). The location of the study intersection is shown in Figure 4.1.




Figure 4.1 Study Intersections

4.2 Background Traffic Volumes

To understand the existing traffic conditions, traffic surveys were undertaken by Austraffic during the AM and PM peak periods on 7th September 2023 for the Peregrine Drive / Forest Hill Fernvale Road intersection and the Park Street / Prospect Street intersection.

The surveyed and adopted peak periods have been summarised in Table 4.1 and a copy of the traffic survey data is enclosed in Appendix B.

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Impact Assessment

www.burchills.com.au

Page 7



Table 4.1 Adopted Peak Periods

Intersection ID	Surveyed Peak Periods			
	АМ	PM		
Peregrine Drive / Forest Hill Fernvale Road	8:00AM – 9:00AM	3:00PM - 4:00PM		
Park Street / Prospect Street	8:00AM – 9:00AM	3:00PM - 4:00PM		
Adopted Hourly Peak Periods	8:00AM — 9:00AM	3:00PM - 4:00PM		

4.3 Traffic Growth

Burchills reviewed TMR's annual segment reports for the Forest Hill Fernvale Road State-controlled road to provide an indication of traffic growth along the study network within the last 10 years. The subject site is located within close proximity to a TMR count site (32101). The AADT data demonstrates minimal traffic growth over the previous 10 years; however 1.27% growth has been recorded in the previous year (2018-2019). This growth rate has been adopted for a conservative approach and applied to Park Street, Prospect Street and Forest Hill Fernvale Road.

No growth has been applied to the residential catchment on Peregrine Drive, as it is assumed to be a closed catchment and fully developed.

4.4 Traffic Generation

In order to determine the traffic likely to be generated by the development, reference has been made to the RTA Guide to Traffic Generating Developments (GTGD) October 2002.

Table 4.2 summarises the trip generation rates, and trip generation adopted for the traffic assessment.

Table 4.2 Development Traffic Generation

Land Use	Yield	Trip Generation Rates		Trip Generation		Source
Land Ose	Helu	AM Peak	PM Peak	AM Peak	PM Peak	Jource
Low density residential	377 dwellings	0.85 trips per dwelling	0.85 trips per dwelling	321 vph	321 vph	GTGD
TOTAL		-	-	321 vph	321 vph	-

Client: Lowood One Pty Ltd

Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Impact Assessment



4.5 Traffic Distribution

The surrounding road network and attractors have been analysed to determine the external distributions for the development traffic, as well as precedent from the traffic survey data obtained.

The distribution of development trips on the network has been determined from the distribution of trips from the Peregrine Drive residential catchment to the west of the subject site (i.e. based on the traffic survey data from 7th September, 2023). It is assumed that 25% of trips to / from the east will occur via the local road network i.e. via Williams Street.

Further details regarding the adopted traffic distributions are provided at Appendix D.

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Impact Assessment Page 9



5. Traffic Assessment Criteria

5.1 Assessment Scenarios

In accordance with TMR's GTIA, the impact assessment year for the development impacts on the external road network should be the year of opening.

A year of opening of 2025 has been assumed. Table 5.1 summarises the impact assessment scenarios.

Table 5.1 Impact Assessment Scenarios

Impact Assessment Scenario	Study Intersections
2025 BG	 Peregrine Drive / Forest Hill Fernvale Road Park Street / Prospect Street Forest Hill Fernvale Road / site access
2025 BG + DEV	 Peregrine Drive / Forest Hill Fernvale Road Park Street / Prospect Street Forest Hill Fernvale Road / site access
2035 BG	Forest Hill Fernvale Road / site access
2035 BG + DEV	Forest Hill Fernvale Road / site access

5.2 Assessment Criteria

The performance of the intersections has been analysed by using SIDRA Intersection 9 software. SIDRA is an industry recognised analysis tool that estimates the capacity and performance of intersections based on input parameters, including geometry and traffic volumes, and provides estimates of an intersection's Degree of Saturation (DOS), queues and delays.

5.2.1 Intersection Delay

The TMR GTIA recognises the intersection delay as a greater indicator of intersection performance in comparison to the previous TMR GARID's focus on the degree of saturation (DOS) criteria. The TMR GTIA appreciates that in urban networks, the DOS of an intersection may not be the most accurate representation of the intersection's operation as it is expected that existing intersections are approaching capacity with the growth of our cities.

Furthermore, for priority-controlled intersections and roundabouts, where the average peak hour delay for any movement exceeds 42 seconds, as outlined in the GTIA, the intersection should be upgraded for safety purposes. At an individual intersection level, where this threshold has been exceeded, Burchills Engineer has made further comments.

Client: Lowood One Pty Ltd

Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Impact Assessment





5.2.2 Intersection Degree of Saturation (DoS)

While the movement delay is considered to provide a better indication of intersection performance and safety for priority-controlled intersections and roundabouts, the DOS should still be considered when assessing the performance of the intersection.

Table 5.2 provides the DOS thresholds adopted for the assessment.

Table 5.2 Adopted Intersection Performance Thresholds - Degree of Saturation

Intersection Treatment	DOS Threshold
Signalised Intersections	Less than or equal to 0.90
Roundabouts	Less than or equal to 0.85
Priority Controlled Intersections	Less than or equal to 0.80

Source: TMR Guidelines for Road Impacts Development

— www.burchills.com.au

6. SIDRA Assessment

Peregrine Drive / Forest Hill Fernvale Road

The existing intersection is currently a priority-controlled T-intersection arrangement. The aerial and SIDRA-assessed layout is illustrated in Figure 6.1.




Figure 6.1 Aerial and SIDRA Layout - Peregrine Drive / Forest Hill Fernvale Road

The result of the SIDRA assessment is summarised in Figure 6.1. The SIDRA layouts and detailed results are included in Appendix C.

Table 6.1 SIDRA Results - Peregrine Drive / Forest Hill Fernvale Road

	AN	I Peak Period	PM Peak Period			
Scenarios	DOS	Critical Mvmt Delay (s)	95 th %ile Queue (m)	DOS	Critical Mvmt Delay (s)	95 th %ile Queue (m)
2025 BG	0.19	12	4	0.19	12	3
2025 BG + DEV	0.20	12	5	0.20	12	3

As shown in Table 6.1, the T-intersection of Peregrine Drive / Forest Hill Fernvale Road performs within the acceptable thresholds (DOS <0.80 and delay <42 seconds) in all scenarios.

As such, the intersection is anticipated to operate satisfactorily following the year of opening for the development.

Lowood One Pty Ltd

Doc No.: BE230128-RP-TIA-04 Doc Title: Traffic Assessment Report

6.2 Park Street / Prospect Street

The existing intersection is currently a priority-controlled T-intersection arrangement. The aerial and SIDRA-assessed layout is illustrated in Figure 6.2.



Figure 6.2 Aerial and SIDRA Layout - Park Street / Prospect Street

The result of the SIDRA assessment is summarised in Table 6.2. The SIDRA layouts and detailed results are included in Appendix D.

AM Peak Period PM Peak Period 95th %ile **Scenarios** Critical Critical 95th %ile DOS DOS **Mvmt Delay** Queue **Mvmt Delay** Queue (s) (m) (s) (m) 2025 BG 7 0.26 8 9 0.26 8 2025 BG + DEV 0.34 9 0.37 13 9 13

Table 6.2 SIDRA Results - Park Street / Prospect Street

As shown in Table 6.2, the T-intersection of Park Street / Prospect Street performs within the acceptable thresholds (DOS <0.80 and delay <42 seconds) in all scenarios.

As such, the intersection is anticipated to operate satisfactorily following the year of opening for the development.

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report

6.3 Forest Hill Fernvale Road / Site Access

The proposed intersection is currently a priority-controlled T-intersection arrangement. The concept layout and SIDRA-assessed layout is illustrated in Figure 6.3.




Figure 6.3 Concept Layout and SIDRA Layout - Forest Hill Fernvale Road / Site Access

The result of the SIDRA assessment is summarised in Table 6.3. The SIDRA layouts and detailed results are included in Appendix C.

	AN	AM Peak Period			PM Peak Period		
Scenarios	DOS	Critical Mvmt Delay (s)	95 th %ile Queue (m)	DOS	Critical Mvmt Delay (s)	95 th %ile Queue (m)	
2025 BG + DEV	0.26	10	8	0.22	10	5	
2035 BG + DEV	0.29	10	9	0.25	11	5	

Table 6.3 SIDRA Results - Forest Hill Fernvale Road / Site Access

As shown in Table 6.3, the T-intersection of Forest Hill Fernvale Road / Site Access performs within the acceptable thresholds (DOS <0.80 and delay <42 seconds) in all scenarios.

As such, the intersection is anticipated to operate satisfactorily following the year of opening and the 10-year design horizon for the development.

6.4 Network Delay Impact

In accordance with the GTIA requirements for no net worsening to baseline road network operations, this assessment has investigated the delay impact of the development traffic on the network. The assessment has reviewed whether the increase in average delay at the study intersections exceeds 5%. The average delay has been calculated as per the guidance in the GTIA illustrated in Figure 6.4, taking the aggregate average delay across the intersections for both the baseline scenario (2025 BG) and the with development scenario (2025 BG + DEV).

Client: Lov

Client: Lowood One Pty Ltd Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report

$$ID = \sum_{i=1}^{n} WD - \sum_{i=1}^{n} BC$$

where:

ID is aggregate intersection-delay impact vehicle-minutes.

WD is 'with development' intersection vehicle-minutes for design peak periods. This is calculated by multiplying the 'with development' average delay by movement to the base case volume on each movement, thus not counting the impact as delays to development traffic, only to pre-existing traffic that is affected by these additional delays.

BC is base case intersection vehicle-minutes for design peak periods n is the number of intersections in the impact assessment area

i is each intersection within the impact assessment area.

Source: TMR GTIA

Figure 6.4 Network Delay Impact

The results of the network impact assessment are summarized in Table 6.4.

Table 6.4 Intersection Delay Impact - Forest Hill Fernvale Road

Assessment Scenario	Aggregate Delay (veh-min)		
	AM Peak	PM Peak	
BG Volumes	1331	1390	
2025 BG	54.62	59.96	
2025 BG + DEV	59.48	67.17	
Difference (Development Impact)	4.86	7.21	
Development Delay Impact (%)	8.90%	12.0%	
Average Delay Impact (%)	10.5%		

As shown in Table 6.4, the network average delay impact is 10%, which exceeds the 5% threshold. However, mitigation measures are not warranted on the State-controlled road network on the basis of the following:

 The overall Degree of Saturation (DOS) and delays for each of the analysed intersections fall well within acceptable limits (i.e. DOS <0.80 and delays <42s) for both pre- and postdevelopment scenarios, which indicates that neither of the intersections are approaching their capacities;

— www.burchills.com.au

The experience you deserve

- Whilst the increase in traffic resulting from the development does increase movement delays by about 2 seconds at most, delays at each intersection still remain under 10 seconds in the post development scenario; and
- It is anticipated that the provision of the additional intersection on Forest Hill Fernvale Road
 will reduce right turn volumes and delays (westbound) at the Park Street / Prospect Street
 intersection, as residents within the existing Williams Street catchment and surrounds will
 utilize the internal road network to travel to / from the west, rather than passing through the
 Park Street / Prospect Street intersection.

On the basis of the above the impacts generated by the development on the external road network are considered to be satisfactory from a traffic engineering perspective.

Client: Lowood One Pty Ltd

Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Assessment Report



7. Car Parking Assessment

7.1 Car Parking Requirements

The SRC Transport, Access and Parking Code specifies a parking rate of 2 spaces per dwelling for dwelling houses. This is a total parking requirement of 754 car parking spaces across the site.

7.2 Car Parking Provision

It is anticipated that each dwelling will contain a double garage for a total of 754 car parking spaces across the site.

7.3 Suitability of Car Parking

The car parking provision satisfies the minimum requirements of the Transport, Access and Parking Code and is expected to meet the parking demands generated by the development.

www.burchills.com.au

8. Design Review

8.1 Overview

Burchills Engineering Solutions has undertaken a detailed review of the proposed site layout to ensure compliance with relevant standards and guidelines, including:

- Somerset Regional Council Planning Scheme;
- Austroads Guide to Road Design Part 4a (AGRD);
- Institute of Public Works Engineering Australasia (IPWEA) Street Design Manual (version 21 August 2020)
- Australian/New Zealand Standard AS2890.1:2004 Parking Facilities

8.2 Access Assessment

8.2.1 Turn Warrants Assessment

A turn warrant assessment has been undertaken in accordance with Department of Transport and Main Roads (DTMR) Road Planning and Design Manual Edition 2: Volume 3 Supplement to Austroads Guide to Road Design Part 4A: Unsignalised Intersections August 2014. A summary of the traffic movement parameters considered is shown in Figure 8.1 below.




Figure 4A-2 - Calculation of the major road traffic volume parameter 'Q_M'

Figure 8.1 Turn Warrants Qm Traffic Flow Calculation

The adopted volumes for the 10-year design horizon scenario for the site access intersection turn warrant assessment are shown in Table 8.1 with the turn warrant diagram shown in Figure 8.2.

Table 8.1 Site Access Trips Peak Hours

Traffic Volume	AM peak hour	PM peak hour
Q _{T1} (westbound)	254	443
Q _{T2} (eastbound)	433	279

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report

www.burchills.com.au

Page 18

QL	33	33
QR	48	144
Qм Left	433	279
Q _M Right	720	755




Figure 8.2 Turn Warrant Assessment (10-Year Design Horizon)

The assessment above indicates that the site access intersection will require the provision of a Channelised Right-turn (CHR) and an Auxiliary Left Turn (AUL) treatment in the 10-year design horizon scenario.

The site access intersection has been designed based on the above requirements and in accordance with Austroads Guide to Road Design Part 4a.

A concept layout of the intersection is shown in Figure 8.3 below.




Figure 8.3 Site Access Intersection Concept Layout

Www.burchills.com.au

8.2.2 Sight Distance

The safe intersection sight distance (SISD) at the proposed site access intersection on Forest Hill Fernvale Road has been assessed in accordance with Austroads Guide to Road Design, Part 4a, as shown in Table 8.2 and Figure 8.4 below.

Table 8.2 SISD Assessment at Site Access Intersection

Direction	Design Speed	SISD Requirement	Available	Compliance
Looking east	90km/h*	214m	>700m	Yes
Looking west	90km/h	214m	>450m	Yes

^{*}Note: the speed limit changes to 60km/h immediately to the east of the subject site; however the sight distance has been assessed at 90km/h for a conservative approach.





Figure 8.4 Sight Lines from Site Access Location Looking East (left) and West (right)

As shown above, the site benefits from ample sight lines in both directions. The SISD at the proposed site access intersection complies with the requirements of AGRD Part 4a.

8.2.3 Safety Assessment on Forest Hill Fernvale Road

The crash data on the road network surrounding the subject site (i.e. between the study intersections on Forest Hill Fernvale Road) has been investigated over the past 5-year period (2017 to 2022). The crash data is summarized in Table 8.3 below.

Table 8.3 Crash Data on Forest Hill Fernvale Road (2017-2022)

Crash ID	Date	Conditions	Severity	DCA Code	Description
151779	November 2019	Daylight, clear	Hospitalisation	705	Off path straight: out of control off carriageway

As shown above, only one incident has been recorded in the previous 5 year period. Additionally, it was a single vehicle incident.

The crash data on Forest Hill Fernvale Road does not identify any recurring trends.

— www.burchills.com.au

8.3 Internal Road Network

8.3.1 Road Widths and Hierarchy

As the internal road network will be managed by SRC, the internal road widths have been assessed against the SRC Standard Drawings.

The road characteristics and design requirements are outlined in Table 8.4 below.

Table 8.4 Road Width Assessment

Road Hierarchy Classification	Road Reserve Requirement	Road Reserve Provision	Carriageway Width Requirement	Carriageway Provision	Compliance
Access Street (40km/h)	Min. 16m	Min. 20m	Min. 8m	Min. 8m	Yes
Collector (60km/h)	Min. 20m	Min. 20m	Min. 10m	Min. 10m	Yes

On the basis of the above, the proposed internal road hierarchy is considered to be satisfactory from a traffic engineering perspective.

8.3.2 Road Capacities

The road capacities of the internal road network have been assessed according the proposed road hierarchy and SRC's Planning Scheme Policy 6.5.8 – Roadwork Design Standards.

Table 8.5 Road Capacity Assessment

Road Hierarchy Classification	Capacity	Max. No. of Lots Served	Compliance
Access Street (40km/h)	75 dwellings	~72 dwellings	Yes
Collector Street (60km/h)	300 dwellings	283 dwellings*	Yes

^{*}Note: it has been assumed that 25% of dwellings will enter and exit the development via Williams Street, i.e. the local road network

As shown above, the proposed road hierarchy has sufficient capacity to cater for the expected traffic demands within the development.

8.3.3 Intersection Spacing

The recommended internal intersection spacing has been assessed based on the IPWEA Street Design Manual requirements, as indicated in Table 8.6.

Table 8.6 Intersection Spacing Assessment

Road	Minimum Requirements	Minimum Identified	Compliance
Local access roads	40m	60m	Yes

The assessment indicates that intersection spacing proposed for the internal local access roads meet the minimum requirements for IPWEA Street Design Manual.

Client: Lowood One Pty Ltd

Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Assessment Report



8.3.4 Active Transport Provisions

Pedestrian footpaths are proposed throughout the development. The footpaths are a minimum of 1.5m wide in accordance with Somerset Regional Council's Standard Drawing SRC-ROAD-019.

8.4 Servicing

8.4.1 Service Vehicle Requirements

The SRC Planning Scheme does not specify service vehicle requirements for dwelling houses. However, it is assumed that access will be required for side-lift Waste Collection Vehicles (WCV) as well as moving trucks (8.8m long medium rigid vehicle, MRV).

8.4.2 Waste Collection

Waste will be collected kerbside via Council's waste collection service. Wheelie bins are proposed to store the waste for each dwelling.

8.4.3 Swept Path - 9.9m WCV

A swept path assessment has been undertaken for the proposed WCV, as shown in the swept paths in Appendix E. The swept path assessment indicates that the WCV can enter and exit the site in a forward gear.

Client: Lowood One Pty Ltd
Doc No.: BE230128-RP-TIA-04

Doc No.: BE230128-RP-11A-04

Doc Title: Traffic Assessment Report

Page 22

9. Conclusions

Burchills Engineering Solutions has been engaged by Lowood One Pty Ltd to provide a Traffic Impact Assessment (TIA) for the proposed residential development at 2893 Forest Hill Fernvale Road, Lowood.

The following key points summarise the findings from the traffic impact assessment undertaken herein:

- The proposed development is comprised of 358 residential lots (including 19 duplex lots) for a total of 377 low density residential dwellings;
- Access to the development is proposed via a new access intersection on Forest Hill Fernvale Road, which includes an auxiliary left turn lane and channelised right turn lane in accordance with Austroads Guide to Road Design Part 4a:
- Pedestrian paths are provided throughout the development;
- Each dwelling will benefit from a double garage, satisfying the minimum requirements of the SRC Transport, Access and Parking Code;
- The internal road network complies with the road design requirements outlined within the Somerset Regional Council Planning Scheme and the IPWEA Street Design Manual:
- The site is anticipated to generate in the order of 321 vehicle movements during both the AM and PM peak periods;
- The operation of the Forest Hill Fernvale Road / site access intersection has been assessed using SIDRA intersection 9.1. The results indicate that the site access intersection will operate within acceptable performance thresholds in the post-development scenario for the year of opening (2025) and 10-year design horizon (2035);
- The adjacent State-controlled intersections (Peregrine Drive / Forest Hill Fernvale Road, Park Road / Prospect Street) operate within acceptable performance thresholds in the postdevelopment scenario for the year of opening (2025);
- A delay assessment was undertaken of the adjacent State-controlled intersections. Whilst the 5% threshold was exceeded, overall delay impacts to the State-controlled road network are expected to be low and do not warrant mitigation measures;
- Swept path analysis indicates that a side lift WCV can traverse the internal road network to collect waste, entering and exiting the site in a forward gear.

Lowood One Pty Ltd

www.burchills.com.au

Doc No.: BE230128-RP-TIA-04 Doc Title: Traffic Assessment Report

The experience you deserve

Appendix A – Site Layout

Lowood One Pty Ltd Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report Page 24 281





DEVELOPMENT SUMMARY

Prepared for: LOWOOD ONE PTY LTD

Designer: QT
Checked: JC
Date: 27.03.24

MASTER PLAN
2983 FOREST HILL FERNVALE RD,
LOWOOD QLD 4311

SCALE

15 0 15 30 45 60 75 (metres)

SCALE 15 0 15 30 45 60 75 (metre 1: 1500 (FULL SIZE)

BE230128-00-SK001-B



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Emaii: admin@burchills.com.au Coote Burchills Englineering Pty Ltd ABN 76 166 942 365



LEGEND

DEVELOPMENT SITE BOUNDARY

—— PROPOSED LOT BOUNDARY

----- PROPOSED ROAD CONTROL LINE

———— W———— EXISTING Ø150 WATER MAIN


— RM — — — EXISTING SEWER RISING MAIN

—— OH — — EXISTING OVERHEAD ELECTRIC

-----> -----> EXISTING FLOWPATH / WATERWAY

———— S ———— EXISTING SEWER MAIN

—— C— — EXISTING COMMS



PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCIL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	10.04.24
VFR	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:

CONCEPT ENGINEERING **DRAWINGS**

DRAWING TITLE:

INTERSECTION FUNCTIONAL PLAN

DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER:	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AN BURCHILLS ENGIN	D ON BEHALF OF IEERING SOLUTIONS	S ABN 76 166 942 365

SCALE: AS NOTED DATUM : AHD PROJECT No.: DRAWING No.: VERSION: SK320 BE230128-00

INTERSECTION FUNCTIONAL PLAN

PRELIMINARY NOT FOR CONSTRUCTION OR TENDER

The experience you deserve

Appendix B - Traffic Survey

Lowood One Pty Ltd Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report Page 25 284

- www.burchills.com.au


Site No.: 1 Weather: Fine

Location: Forest Hill Fernvale Road/Peregrine Drive, Lowood

Day/Date: Thursday, 7 September 2023

Summary: AM Peak: Hour ending - 9:00 AM

PM Peak: Hour ending - 4:00 PM



Note: 3.28% = proportion of selected vehicle classification as a percentage of total vehicles

Peregrine Drive (south)


Site No.: 1 Weather: Fine

Location: Forest Hill Fernvale Road/Peregrine Drive, Lowood

Day/Date: Thursday, 7 September 2023

Summary: AM Peak: Hour ending - 9:00 AM

PM Peak: Hour ending - 4:00 PM



Note: 3.28% = proportion of selected vehicle classification as a percentage of total vehicles

Peregrine Drive (south)


Site No.: 2 Weather: Fine

Location: Prospect Street/Park Street, Lowood

Day/Date: Thursday, 7 September 2023

Summary: AM Peak: Hour ending - 9:00 AM

PM Peak: Hour ending - 4:00 PM



Note: 3.28% = proportion of selected vehicle classification as a percentage of total vehicles


Site No.: 2 Weather: Fine

Location: Prospect Street/Park Street, Lowood

Day/Date: Thursday, 7 September 2023

Summary: AM Peak: Hour ending - 9:00 AM

PM Peak: Hour ending - 4:00 PM



Note: 3.28% = proportion of selected vehicle classification as a percentage of total vehicles


The experience you deserve

Appendix C – Traffic Flow Diagrams

Client: Lowood One Pty Ltd Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report Page 26


AM Peak 8:00AM - 9:00AM (PM Peak) 3:00PM - 4:00PM



BE230128_2983 Forest Hill Fernvale Road

2023 Background Traffic Volumes






BE230128_2983 Forest Hill Fernvale Road

2023 Existing In / Out Splits






BE230128_2983 Forest Hill Fernvale Road

Development Trips



Growth factor (Forest Hill Fernvale Road): 1.03
Assessment year: 2025
AM Peak
(PM Peak)




BE230128_2983 Forest Hill Fernvale Road

2025 Background Traffic Volumes



Assessment year: 2025 AM Peak (PM Peak)




BE230128_2983 Forest Hill Fernvale Road

2025 Background + Development Traffic



Growth factor (Forest Hill Fernvale Road): 1.15
Assessment year: 2035
AM Peak
(PM Peak)




BE230128_2983 Forest Hill Fernvale Road

2035 Background Traffic Volumes



Assessment year: 2035 AM Peak (PM Peak)



BE230128_2983 Forest Hill Fernvale Road

2035 Background + Development Traffic



The experience you deserve

Appendix D - SIDRA Outputs

Client: Lowood One Pty Ltd

Doc No.: BE230128-RP-TIA-04
Doc Title: Traffic Assessment Report

297

Page 27

USER REPORT FOR SITE

Project: Forest Hill Fernvale Road_Intersection Models

Output produced by SIDRA INTERSECTION Version: 9.1.4.221 Template: Movement Summary

V Site: 101 [BG2025 Peregrine Drive / Forest Hill Fernvale Road - AM Peak (Site Folder: BG2025)]

Peregrine Drive / Forest Hill Fernvale Road BG2025 AM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	le Mo	vement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service	95% B Que [Veh. veh		Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
South	Pere	grine Driv	е												
1	L2	All MCs	8	5.0	8	5.0	0.164	6.6	LOSA	0.6	4.4	0.60	0.80	0.60	48.5
3	R2	All MCs	69	5.0	69	5.0	0.164	12.2	LOS B	0.6	4.4	0.60	0.80	0.60	48.5
Appro	ach		78	5.0	78	5.0	0.164	11.6	LOS B	0.6	4.4	0.60	0.80	0.60	48.5
East: I	orest	Hill Fern	vale Roa	ad											
4	L2	All MCs	22	5.0	22	5.0	0.012	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
5	T1	All MCs	218	5.0	218	5.0	0.115	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		240	5.0	240	5.0	0.115	0.5	NA	0.0	0.0	0.00	0.05	0.00	59.2
West:	Fores	t Hill Fern	vale Ro	ad											
11	T1	All MCs	352	5.0	352	5.0	0.186	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
12	R2	All MCs	12	5.0	12	5.0	0.011	6.5	LOS A	0.0	0.3	0.33	0.57	0.33	51.5
Appro	ach		363	5.0	363	5.0	0.186	0.3	NA	0.0	0.3	0.01	0.02	0.01	59.6
All Vel	nicles		681	5.0	681	5.0	0.186	1.7	NA	0.6	4.4	0.07	0.12	0.07	57.9

V Site: 101 [BG2025 Peregrine Drive / Forest Hill Fernvale Road - PM Peak (Site Folder: BG2025)]

Peregrine Drive / Forest Hill Fernvale Road BG2025 PM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	cle Mo	ovement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival ows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		lack Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
South	: Pere	grine Driv	e												
1	L2	All MCs	9	5.0	9	5.0	0.096	7.4	LOSA	0.3	2.5	0.59	0.80	0.59	48.5
3	R2	All MCs	35	5.0	35	5.0	0.096	12.8	LOS B	0.3	2.5	0.59	0.80	0.59	48.5
Appro	ach		44	5.0	44	5.0	0.096	11.7	LOS B	0.3	2.5	0.59	0.80	0.59	48.5
East:	Forest	Hill Fern	vale Ro	ad											
4	L2	All MCs	68	5.0	68	5.0	0.038	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
5	T1	All MCs	363	5.0	363	5.0	0.192	0.1	LOS A	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		432	5.0	432	5.0	0.192	0.9	NA	0.0	0.0	0.00	0.09	0.00	58.6
West:	Fores	t Hill Ferr	vale Ro	ad											
11	T1	All MCs	237	5.0	237	5.0	0.125	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
12	R2	All MCs	12	5.0	12	5.0	0.013	7.6	LOSA	0.0	0.4	0.46	0.63	0.46	50.9
Appro	ach		248	5.0	248	5.0	0.125	0.4	NA	0.0	0.4	0.02	0.03	0.02	59.4
All Ve	hicles		724	5.0	724	5.0	0.192	1.4	NA	0.3	2.5	0.04	0.11	0.04	58.2

V Site: 101 [BG2025_Park Street / Prospect Street - AM Peak (Site Folder: BG2025)]

Park Street / Prospect Street BG2025 AM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	cle Mo	vement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East:	Prosp	ect Street													
5	T1	All MCs	143	5.0	143	5.0	0.091	0.2	LOSA	0.2	1.1	0.10	0.12	0.10	58.9
6	R2	All MCs	21	5.0	21	5.0	0.091	6.3	LOS A	0.2	1.1	0.10	0.12	0.10	55.9
Appro	ach		164	5.0	164	5.0	0.091	0.9	NA	0.2	1.1	0.10	0.12	0.10	58.5
North:	: Park	Street													
7	L2	All MCs	16	5.0	16	5.0	0.151	6.4	LOSA	0.5	3.8	0.45	0.71	0.45	51.0
9	R2	All MCs	106	5.0	106	5.0	0.151	8.1	LOS A	0.5	3.8	0.45	0.71	0.45	50.7
Appro	ach		122	5.0	122	5.0	0.151	7.9	LOSA	0.5	3.8	0.45	0.71	0.45	50.7
West:	Prosp	ect Street	t												
10	L2	All MCs	215	5.0	215	5.0	0.256	5.7	LOSA	1.2	8.7	80.0	0.27	0.08	54.9
11	T1	All MCs	219	5.0	219	5.0	0.256	0.0	LOS A	1.2	8.7	0.08	0.27	0.08	57.1
Appro	ach		434	5.0	434	5.0	0.256	2.9	NA	1.2	8.7	0.08	0.27	0.08	56.0
All Ve	hicles		720	5.0	720	5.0	0.256	3.3	NA	1.2	8.7	0.15	0.31	0.15	55.6

V Site: 101 [BG2025_Park Street / Prospect Street - PM Peak (Site Folder: BG2025)]

Park Street / Prospect Street BG2025 PM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	cle Mo	ovement	Perfor	man	се										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East:	Prosp	ect Street													
5	T1	All MCs	234	5.0	234	5.0	0.133	0.0	LOS A	0.1	0.7	0.03	0.04	0.03	59.6
6	R2	All MCs	14	5.0	14	5.0	0.133	5.7	LOS A	0.1	0.7	0.03	0.04	0.03	56.5
Appro	ach		247	5.0	247	5.0	0.133	0.3	NA	0.1	0.7	0.03	0.04	0.03	59.4
North	: Park	Street													
7	L2	All MCs	13	5.0	13	5.0	0.256	6.0	LOSA	1.0	6.9	0.45	0.70	0.45	51.0
9	R2	All MCs	202	5.0	202	5.0	0.256	7.9	LOS A	1.0	6.9	0.45	0.70	0.45	50.7
Appro	ach		215	5.0	215	5.0	0.256	7.8	LOSA	1.0	6.9	0.45	0.70	0.45	50.8
West:	Prosp	ect Stree	t												
10	L2	All MCs	178	5.0	178	5.0	0.167	5.7	LOSA	0.8	5.6	0.07	0.35	0.07	54.3
11	T1	All MCs	99	5.0	99	5.0	0.167	0.0	LOS A	0.8	5.6	0.07	0.35	0.07	56.4
Appro	ach		277	5.0	277	5.0	0.167	3.7	NA	0.8	5.6	0.07	0.35	0.07	55.0
All Ve	hicles		739	5.0	739	5.0	0.256	3.8	NA	1.0	6.9	0.17	0.35	0.17	55.0

SIDRA INTERSECTION 9.1 | Copyright © 2000-2023 Akcelik and Associates Pty Ltd | sidrasolutions.com
Organisation: BURCHILLS ENGINEERING SOLUTIONS | Licence: NETWORK / 1PC | Created: Wednesday, 24 April 2024 12:27:39 PM
Project: \BES-SVR01\Projects\2023\BE230128_2983 Forest Hill Fernvale Rd, Lowood\!Traffic\SIDRA\Forest Hill Fernvale Road_Intersection Models.sip9

USER REPORT FOR SITE

Project: Forest Hill Fernvale Road_Intersection Models

Output produced by SIDRA INTERSECTION Version: 9.1.4.221 Template: Movement Summary

V Site: 101 [DEV2025_Park Street / Prospect Street - PM Peak (Site Folder: DEV2025)]

Park Street / Prospect Street DEV2025 PM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	ele Mo	vement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival ows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of Jeue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East:	Prospe	ect Street													
5	T1	All MCs	304	5.0	304	5.0	0.169	0.0	LOSA	0.1	0.7	0.02	0.03	0.02	59.7
6	R2	All MCs	13	5.0	13	5.0	0.169	5.7	LOSA	0.1	0.7	0.02	0.03	0.02	56.6
Appro	ach		317	5.0	317	5.0	0.169	0.2	NA	0.1	0.7	0.02	0.03	0.02	59.6
North	Park	Street													
7	L2	All MCs	12	5.0	12	5.0	0.369	6.6	LOSA	1.7	12.6	0.55	0.81	0.68	49.9
9	R2	All MCs	262	5.0	262	5.0	0.369	9.5	LOS A	1.7	12.6	0.55	0.81	0.68	49.6
Appro	ach		274	5.0	274	5.0	0.369	9.4	LOS A	1.7	12.6	0.55	0.81	0.68	49.7
West:	Prosp	ect Street	i												
10	L2	All MCs	208	5.0	208	5.0	0.195	5.7	LOSA	0.9	6.8	0.06	0.35	0.06	54.3
11	T1	All MCs	116	5.0	116	5.0	0.195	0.0	LOSA	0.9	6.8	0.06	0.35	0.06	56.4
Appro	ach		324	5.0	324	5.0	0.195	3.7	NA	0.9	6.8	0.06	0.35	0.06	55.1
All Ve	hicles		915	5.0	915	5.0	0.369	4.2	NA	1.7	12.6	0.19	0.38	0.23	54.7

V Site: 101 [DEV2025 Peregrine Drive / Forest Hill Fernvale Road - AM Peak (Site Folder: DEV2025)]

Peregrine Drive / Forest Hill Fernvale Road DEV2025 AM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	le Mo	vement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		ack Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
South	Pere	grine Driv	e												
1	L2	All MCs	8	5.0	8	5.0	0.173	6.7	LOSA	0.6	4.6	0.61	0.82	0.61	48.1
3	R2	All MCs	69	5.0	69	5.0	0.173	12.9	LOS B	0.6	4.6	0.61	0.82	0.61	48.1
Appro	ach		78	5.0	78	5.0	0.173	12.2	LOS B	0.6	4.6	0.61	0.82	0.61	48.1
East: I	orest	Hill Fern	vale Ro	ad											
4	L2	All MCs	22	5.0	22	5.0	0.012	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
5	T1	All MCs	233	5.0	233	5.0	0.123	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		255	5.0	255	5.0	0.123	0.5	NA	0.0	0.0	0.00	0.05	0.00	59.2
West:	Fores	t Hill Fern	vale Ro	ad											
11	T1	All MCs	369	5.0	369	5.0	0.196	0.1	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
12	R2	All MCs	12	5.0	12	5.0	0.011	6.6	LOS A	0.0	0.3	0.35	0.58	0.35	51.5
Appro	ach		381	5.0	381	5.0	0.196	0.2	NA	0.0	0.3	0.01	0.02	0.01	59.6
All Vel	nicles		714	5.0	714	5.0	0.196	1.6	NA	0.6	4.6	0.07	0.12	0.07	58.0

V Site: 101 [DEV2025 Peregrine Drive / Forest Hill Fernvale Road - PM Peak (Site Folder: DEV2025)]

Peregrine Drive / Forest Hill Fernvale Road DEV2025 PM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	le Mo	ovement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		ack Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
South	: Pere	grine Driv	e												
1	L2	All MCs	9	5.0	9	5.0	0.100	7.5	LOSA	0.4	2.6	0.60	0.81	0.60	48.2
3	R2	All MCs	35	5.0	35	5.0	0.100	13.4	LOS B	0.4	2.6	0.60	0.81	0.60	48.2
Appro	ach		44	5.0	44	5.0	0.100	12.1	LOS B	0.4	2.6	0.60	0.81	0.60	48.2
East:	Forest	Hill Fern	vale Ro	ad											
4	L2	All MCs	68	5.0	68	5.0	0.038	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
5	T1	All MCs	368	5.0	368	5.0	0.195	0.1	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		437	5.0	437	5.0	0.195	0.9	NA	0.0	0.0	0.00	0.09	0.00	58.6
West:	Fores	t Hill Fern	vale Ro	ad											
11	T1	All MCs	260	5.0	260	5.0	0.138	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
12	R2	All MCs	12	5.0	12	5.0	0.013	7.6	LOS A	0.0	0.4	0.46	0.63	0.46	50.9
Appro	ach		272	5.0	272	5.0	0.138	0.4	NA	0.0	0.4	0.02	0.03	0.02	59.5
All Ve	hicles		753	5.0	753	5.0	0.195	1.4	NA	0.4	2.6	0.04	0.11	0.04	58.2

▽ Site: 101 [DEV2025_Park Street / Prospect Street - AM Peak (Site Folder: DEV2025)]

Park Street / Prospect Street DEV2025 AM Peak Site Category: (None) Give-Way (Two-Way)

Vehic	cle Mo	vement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East:	Prosp	ect Street													
5	T1	All MCs	165	5.0	165	5.0	0.103	0.2	LOSA	0.2	1.2	0.10	0.12	0.10	59.0
6	R2	All MCs	20	5.0	20	5.0	0.103	6.6	LOSA	0.2	1.2	0.10	0.12	0.10	56.0
Appro	ach		185	5.0	185	5.0	0.103	0.9	NA	0.2	1.2	0.10	0.12	0.10	58.6
North	Park	Street													
7	L2	All MCs	15	5.0	15	5.0	0.201	6.8	LOSA	0.7	5.0	0.53	0.78	0.53	50.2
9	R2	All MCs	123	5.0	123	5.0	0.201	9.2	LOS A	0.7	5.0	0.53	0.78	0.53	49.9
Appro	ach		138	5.0	138	5.0	0.201	9.0	LOSA	0.7	5.0	0.53	0.78	0.53	50.0
West:	Prosp	ect Street	t												
10	L2	All MCs	283	5.0	283	5.0	0.337	5.7	LOSA	1.7	12.5	0.09	0.27	0.09	54.9
11	T1	All MCs	288	5.0	288	5.0	0.337	0.0	LOS A	1.7	12.5	0.09	0.27	0.09	57.0
Appro	ach		572	5.0	572	5.0	0.337	2.9	NA	1.7	12.5	0.09	0.27	0.09	56.0
All Ve	hicles		895	5.0	895	5.0	0.337	3.4	NA	1.7	12.5	0.16	0.32	0.16	55.5

V Site: 101 [Forrest Hill Fernvale Road and Site Access with Dev 2025 AM - Import (Site Folder: DEV2025)]

Forrest Hill Fernvale Road and Site Access 2025 Site Category: (None) Give-Way (Two-Way)

Vehic	cle Mo	vement	Perfor	man	се				_						
Mov ID	Turn	Mov Class		ows HV]		rival ows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East:	Forres	t Hill Ferr	nvale Ro	ad											
5	T1	All MCs	238	5.0	238	5.0	0.126	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
6	R2	All MCs	51	5.0	51	5.0	0.059	7.8	LOS A	0.2	1.6	0.48	0.69	0.48	50.7
Appro	ach		288	5.0	288	5.0	0.126	1.4	NA	0.2	1.6	0.08	0.12	0.08	58.1
North	: Site A	Access													
7	L2	All MCs	159	5.0	159	5.0	0.263	8.2	LOSA	1.1	7.7	0.54	0.76	0.57	50.0
9	R2	All MCs	25	5.0	25	5.0	0.263	15.8	LOS C	1.1	7.7	0.54	0.76	0.57	49.9
Appro	ach		184	5.0	184	5.0	0.263	9.3	LOSA	1.1	7.7	0.54	0.76	0.57	50.0
West	Forre	st Hill Fer	nvale R	oad											
10	L2	All MCs	35	5.0	35	5.0	0.019	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
11	T1	All MCs	406	5.0	406	5.0	0.215	0.1	LOS A	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		441	5.0	441	5.0	0.215	0.5	NA	0.0	0.0	0.00	0.05	0.00	59.2
All Ve	hicles		914	5.0	914	5.0	0.263	2.5	NA	1.1	7.7	0.14	0.21	0.14	56.8

▼ Site: 101 [Forrest Hill Fernvale Road and Site Access with Dev 2025 PM - Import (Site Folder: DEV2025)]

Forrest Hill Fernvale Road and Site Access 2025 Site Category: (None) Give-Way (Two-Way)

Vehic	cle Mo	vement	Perfor	man	ice										
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East:	Forres	t Hill Ferr	nvale Ro	ad											
5	T1	All MCs	415	5.0	415	5.0	0.220	0.1	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
6	R2	All MCs	152	5.0	152	5.0	0.148	7.0	LOSA	0.6	4.5	0.41	0.65	0.41	51.3
Appro	ach		566	5.0	566	5.0	0.220	1.9	NA	0.6	4.5	0.11	0.18	0.11	57.3
North	: Site A	Access													
7	L2	All MCs	60	5.0	60	5.0	0.137	6.9	LOSA	0.5	3.6	0.52	0.69	0.52	49.7
9	R2	All MCs	22	5.0	22	5.0	0.137	17.9	LOS C	0.5	3.6	0.52	0.69	0.52	49.5
Appro	ach		82	5.0	82	5.0	0.137	9.8	LOSA	0.5	3.6	0.52	0.69	0.52	49.6
West:	Forre	st Hill Fer	nvale R	oad											
10	L2	All MCs	35	5.0	35	5.0	0.019	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
11	T1	All MCs	261	5.0	261	5.0	0.138	0.0	LOS A	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		296	5.0	296	5.0	0.138	0.7	NA	0.0	0.0	0.00	0.07	0.00	59.0
All Ve	hicles		944	5.0	944	5.0	0.220	2.2	NA	0.6	4.5	0.11	0.19	0.11	57.0

V Site: 101 [Forrest Hill Fernvale Road and Site Access with Dev 2035 AM - Import (Site Folder: DEV2035)]

Forrest Hill Fernvale Road and Site Access 2025 Site Category: (None) Give-Way (Two-Way)

Vehicle Movement Performance															
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service		Back Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East: Forrest Hill Fernvale Road															
5	T1	All MCs	267	5.0	267	5.0	0.142	0.0	LOSA	0.0	0.0	0.00	0.00	0.00	59.9
6	R2	All MCs	51	5.0	51	5.0	0.064	8.2	LOS A	0.2	1.7	0.50	0.72	0.50	50.5
Appro	ach		318	5.0	318	5.0	0.142	1.3	NA	0.2	1.7	0.08	0.11	0.08	58.2
North: Site Access															
7	L2	All MCs	159	5.0	159	5.0	0.288	8.9	LOSA	1.2	8.8	0.58	0.81	0.65	49.4
9	R2	All MCs	25	5.0	25	5.0	0.288	18.3	LOS C	1.2	8.8	0.58	0.81	0.65	49.3
Appro	ach		184	5.0	184	5.0	0.288	10.2	LOS B	1.2	8.8	0.58	0.81	0.65	49.4
West: Forrest Hill Fernvale Road															
10	L2	All MCs	35	5.0	35	5.0	0.019	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
11	T1	All MCs	456	5.0	456	5.0	0.241	0.1	LOS A	0.0	0.0	0.00	0.00	0.00	59.9
Appro	ach		491	5.0	491	5.0	0.241	0.5	NA	0.0	0.0	0.00	0.04	0.00	59.3
All Ve	hicles		993	5.0	993	5.0	0.288	2.5	NA	1.2	8.8	0.13	0.21	0.15	56.8

$\overline{f V}$ Site: 101 [Forrest Hill Fernvale Road and Site Access with Dev 2035 PM - Import (Site Folder: DEV2035)]

Forrest Hill Fernvale Road and Site Access 2025 Site Category: (None) Give-Way (Two-Way)

Vehicle Movement Performance															
Mov ID	Turn	Mov Class		lows HV]		rival lows HV] %	Deg. Satn v/c	Aver. Delay sec	Level of Service	95% B Qu [Veh. veh	ack Of eue Dist] m	Prop. Que	Eff. Stop Rate	Aver. No. of Cycles	Aver. Speed km/h
East: Forrest Hill Fernvale Road															
5	T1	All MCs	466	5.0	466	5.0	0.247	0.1	LOS A	0.0	0.0	0.00	0.00	0.00	59.9
6	R2	All MCs	152	5.0	152	5.0	0.154	7.2	LOS A	0.6	4.6	0.44	0.67	0.44	51.2
Appro	ach		618	5.0	618	5.0	0.247	1.8	NA	0.6	4.6	0.11	0.16	0.11	57.5
North: Site Access															
7	L2	All MCs	60	5.0	60	5.0	0.153	7.1	LOSA	0.5	3.9	0.56	0.72	0.56	49.0
9	R2	All MCs	22	5.0	22	5.0	0.153	20.7	LOS C	0.5	3.9	0.56	0.72	0.56	48.9
Appro	ach		82	5.0	82	5.0	0.153	10.8	LOS B	0.5	3.9	0.56	0.72	0.56	49.0
West: Forrest Hill Fernvale Road															
10	L2	All MCs	35	5.0	35	5.0	0.019	5.6	LOSA	0.0	0.0	0.00	0.58	0.00	52.7
11	T1	All MCs	294	5.0	294	5.0	0.156	0.0	LOS A	0.0	0.0	0.00	0.00	0.00	59.9
Appro	Approach 328 5.0 3			328	5.0	0.156	0.6	NA	0.0	0.0	0.00	0.06	0.00	59.1	
All Ve	hicles		1028	5.0	1028	5.0	0.247	2.2	NA	0.6	4.6	0.11	0.18	0.11	57.2

SIDRA INTERSECTION 9.1 | Copyright © 2000-2023 Akcelik and Associates Pty Ltd | sidrasolutions.com
Organisation: BURCHILLS ENGINEERING SOLUTIONS | Licence: NETWORK / 1PC | Created: Wednesday, 24 April 2024 12:23:48 PM
Project: \BES-SVR01\Projects\2023\BE230128_2983 Forest Hill Fernvale Rd, Lowood\!Traffic\SIDRA\Forest Hill Fernvale Road_Intersection Models.sip9


The experience you deserve

Appendix E - Swept Paths

Client: Lowood One Pty Ltd Doc No.: BE230128-RP-TIA-04

Doc Title: Traffic Assessment Report Page 28 310





Prepared for: LOWOOD ONE PTY LTD

WCV SWEPT PATHS
2983 FOREST HILL FERNVALE RD LOWOOD


Designer: ADELE PACKER
Checked: ANGELA WOOD
Date: 24-04-2024

SCALE 15 0 15 30 45 60 75 (metres)

BE230128-SK002



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Englineering Pty Ltd ABN 76 166 942 365





The experience **you deserve**

GOLD COAST OFFICE

P 07 5509 6400 Level 2, 26 Marine Parade, Southport Qld 4215 PO Box 3766, Australia Fair, Southport Qld 4215 **BRISBANE OFFICE**

P 07 3607 6332 Level 14, 167 Eagle Street, Brisbane Qld 4000 PO Box 83, Brisbane Qld 4000


admin@burchills.com.au

www.burchills.com.au

PROPOSED RESIDENTIAL DEVELOPMENT AT 2983 FOREST HILL FERNVALE RD, LOWOOD QUEENSLAND 4311

EARTHWORKS OPW - STAGE 1

CONTRACT BE230128-01A



DRAWING INDEX							
DWG No.	DESCRIPTION						
C000	COVER SHEET						
C200	BULK EARTHWORKS LAYOUT PLAN						
C210	EARTHWORKS SECTIONS						
C220	EARTHWORKS NOTES AND DETAILS						
C250	EROSION & SEDIMENT CONTROL PLAN - EARTHWORKS PHASE						
C251	EROSION & SEDIMENT CONTROL BASIN NOTES AND DETAILS						
C252	EROSION & SEDIMENT CONTROL TYPICAL NOTES AND DETAILS						
C900	HAZARD RISK REGISTER - DESIGN RISKS						

GENERAL NOTES:

ALL DRAWINGS UNDER THIS CONTRACT ARE TO BE READ IN CONJUNCTION WITH THE PROJECT SPECIFICATION

ALL TOPSOIL STRIPPED FROM WORK AREAS SHALL BE STOCKPILED FOR LATER RE-SPREADING TO ALL FOOTPATHS, BATTERS AND ALLOTMENTS.

10. EARTHWORKS (GENERAL)

ALL FILL MATERIAL PLACED SHALL BE COMPACTED AND TRIMMED TO FINAL EARTHWORKS LEVELS AND PROFILES SHOWN ON THE CONTRACT DRAWINGS AND TESTED IN ACCORDANCE WITH THE PROJECT

ALL COMPACTION TESTING UNDER THIS CONTRACT IS TO BE CARRIED OUT TO AS3798 LEVEL 1 STANDARD BY A NATA-ACCREDITED TESTING AUTHORITY. CERTIFICATION FOR ALL EARTHWORKS CONSTRUCTION AND TESTING IS TO BE PROVIDED BY A REGISTERED PROFESSIONAL ENGINEER QUEENSLAND (RPEQ) ENGAGED BY THE CONTRACTOR.

11. COMPACTION STANDARDS

ALL FILL MATERIAL PLACED UNDER THIS CONTRACT SHALL BE COMPACTED IN ACCORDANCE WITH THE PROJECT SPECIFICATION AND CURRENT COUNCIL STANDARDS.

ALL TESTING SHALL BE CARRIED OUT BY AN APPROVED N.A.T.A. TESTING AUTHORITY IN ACCORDANCE WITH THE PROJECT SPECIFICATION AND COUNCIL STANDARDS.

13. "AS CONSTRUCTED" SURVEY

"AS CONSTRUCTED" SURVEY SHALL BE CARRIED OUT BY THE PRINCIPAL'S SURVEYOR AS WORK PROCEEDS.

14. MAINTENANCE OF SITE CONDITION

AT THE COMPLETION OF WORKS THE SITE IS TO BE LEFT IN A CLEAN AND TIDY CONDITION TO THE SATISFACTION OF THE SUPERINTENDENT AND RELEVANT COUNCIL REPRESENTATIVE.

ALL DRAWINGS TO BE READ IN CONJUNCTION WITH: - VEGETATION MANAGEMENT AND TREE CLEARING REQUIREMENTS


> PREPARED FOR LOWOOD ONE PTY LTD




GOLD COAST | BRISBANE | TOOWOOMBA **IPSWICH | MORETON BAY** PHONE: +61 7 5509 6400 FAX: +61 7 5509 6411 EMAIL: ADMIN@BURCHILLS.COM.AU COOTE BURCHILLS ENGINEERING PTY LTD ABN 76 166 942 365

DATE: 24-04-24 VERSION: DRAWING No. BE230128-01A

DESIGNS HAVE BEEN UNDERTAKEN USING SURVEY DATA PROVIDED BY ONE SURVEYORS DATED 6 NOVEMBER 2023





GENERAL EARTHWORKS NOTES:

- 1. ALL EARTHWORKS CONSTRUCTION UNDER THIS CONTRACT IS TO BE PERFORMED STRICTLY IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT PREPARED BY THE PRINCIPAL'S GEOTECHNICAL CONSULTANT.
- 2. ALL COMPACTION TESTING UNDER THIS CONTRACT IS TO BE CARRIED OUT TO AS3798 LEVEL 1 STANDARD BY A NATA-ACCREDITED TESTING AUTHORITY. CERTIFICATION FOR ALL EARTHWORKS CONSTRUCTION AND TESTING IS TO BE PROVIDED BY A REGISTERED PROFESSIONAL ENGINEER QUEENSLAND (RPEQ) ENGAGED BY THE CONTRACTOR.
- 3. ALL DESIGN LEVELS SHOWN ON THE CONTRACT DRAWINGS ARE FINISHED SURFACE LEVELS FOLLOWING TOPSOIL REPLACEMENT.
- 4. ALL STRUCTURAL FILL MATERIAL PLACED SHALL BE COMPACTED TO THE FOLLOWING MINIMUM DENSITY IN ACCORDANCE WITH THE SPECIFICATION AND THE GEOTECHNICAL REPORT:
 - a) 95% DENSITY RATIO FOR GENERAL STRUCTURAL FILL (COHESIVE MATERIAL) b) 98% DENSITY RATIO FOR THE TOP 300mm DEPTH BELOW PAVEMENT SUBGRADE LEVEL (COHESIVE MATERIAL)
- 5. ALL EARTHWORKS BATTERS STEEPER THAN 1 IN 4 ARE TO BE LANDSCAPED IN ACCORDANCE WITH LANDSCAPE ARCHITECTS PLANS.
- EXISTING DAMS ARE TO BE DE-WATERED AND CLEANED-OUT. ALL UNSUITABLE OR SATURATED MATERIAL IS TO BE REMOVED AND REPLACED WITH SELECTED ON-SITE STRUCTURAL FILL MATERIAL AND COMPACTED AS SPECIFIED. FILLING OF DAMS IS TO BE COMPLETED UNDER LEVEL 1 BY GEOTECHNICAL ENGINEER.
- PROVIDE CONDITION SURVEY OF ADJACENT RESIDENTIAL BUILDINGS FOR ALL PROPERTIES LOCATED WITHIN NOMINAL 100m OF EARTHWORKS OPERATIONS. CONDITION SURVEY TO BE UNDERTAKEN BY QUALIFIED PERSONNEL WITH BUILDING EXPERIENCE.


TYPICAL EARTHWORKS SEQUENCE NOTES:


- 1. CONSTRUCT DIVERSION DRAINS AS DIRECTED TO DIVERT SITE RUNOFF AWAY FROM CONSTRUCTION AREAS. ESTABLISH DE-WATERING CONTROLS TO ENSURE THAT THE CONSTRUCTION AREAS REMAIN FREE OF SURFACE WATER AND PONDING.
- 2. FOLLOWING COMPLETION OF CLEARING OPERATIONS AND REMOVAL OF RESIDUAL VEGETATION AND DEBRIS, STRIP TOPSOIL TO A NOMINAL 150mm DEPTH AND PLACE IN TEMPORARY STOCKPILES IN LOCATIONS APPROVED BY THE SUPERINTENDENT.
- PROOF-ROLL AND COMPACT THE PROPOSED FILL AREAS FOLLOWING TOPSOIL STRIPPING, TO THE SATISFACTION OF THE SUPERINTENDENT.
- 4. ANY STRIPPED AREAS WHICH DEMONSTRATE EXCESSIVE MOVEMENT OR DO NOT IMPROVE SUFFICIENTLY UNDER PROOF-ROLLING ARE TO BE REMOVED, REPLACED WITH APPROVED SITE MATERIAL AND COMPACTED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT.
- 5. ANY UNSUITABLE MATERIAL ENCOUNTERED, INCLUDING SILTY MATERIAL AND UN-CONTROLLED FILL IS TO BE EXCAVATED TO THE EXTENTS AND DEPTHS NOMINATED BY THE PRINCIPAL'S GEOTECHNICAL CONSULTANT, REMOVED TO NON-STRUCTURAL FILL AREAS OR TAKEN OFF-SITE AS DIRECTED AND REPLACED WITH APPROVED, COMPACTED FILL MATERIAL.
- PLACE STRUCTURAL FILL MATERIAL FROM SITE EXCAVATIONS TO NOMINATED SITE FILL AREAS, INCLUDING BENCHING AND COMPACTION IN ACCORDANCE WITH THE GEOTECHNICAL REPORT AND TRIMMING AND FINAL PROFILING OF BATTERS.
- 7. PROVIDE GRASSING TO TOPSOILED AREAS AS DIRECTED.

RETAINING WALL NOTES:

- RETAINING WALLS, FOOTINGS, DRAINAGE, BACKFILL AND CONNECTION OF AGGREGATE DRAINS TO STORMWATER DRAINAGE SYSTEM TO BE DESIGNED AND CONSTRUCTED BY THE CONTRACTOR AND CERTIFIED BY AN SUITABLY QUALIFIED RPEQ
- 2. THESE DRAWINGS IDENTIFY SURFACE PROFILES, RETAINING WALL LOCATIONS, AND SETOUT INFORMATION ONLY. REFER TO CONTRACTOR SUPPLIED DRAWINGS FOR RPEQ STRUCTURAL DETAILS, WALL MATERIALS AND COMPACTION SPECIFICATIONS AND CONSTRUCTIBILITY INFORMATION.
- RETAINING WALL DESIGN ENGINEER TO PROVIDE RPEQ FORM 15 STRUCTURAL CERTIFICATE INCLUDING GEOTECHNICAL GLOBAL STABILITY CERTIFICATION BY GEOTECHNICAL ENGINEER. WALL DESIGN TO ASSUME SURCHARGE LOADING BEHIND WALL. DESIGN TO BE IN ACCORDANCE WITH AS4678 INCLUDING ALL REQUIRED DESIGN LOAD CASES AND COMBINATIONS.
- RETAINING WALLS TO BE DESIGNED TO CONSIDER ALL LOADS INCLUDING CONSTRUCTION LOADS AND OPERATIONAL LOADS.
- 5. ANY GEOTECHINCAL INFORMATION PROVIDED BY THE PRINCIPAL OR THE SUPERINTENDENT SHALL BE FOR INFORMATION PURPOSES ONLY. THE CONTRACTOR AND THE RETAINING WALL DESIGN ENGINEER SHOULD SATISFY THEMSELVES OF THE DESIGN SOIL PARAMETERS AND UNDERTAKE AND ADDITIONAL GEOTECHNICAL INVESTIGATION DEEMED NECESSARY BY THE DESIGN ENGINEER.
- 6. THE CONTRACTOR SHALL ENSURE THAT ANY CONFLICT BETWEEN THESE PROJECT DRAWINGS AND THE RETAINING WALL DRAWINGS PREPARED BY THE RETAINING WALL DESIGN ENGINEER IS RESOLVED WITH THE SUPERINTENDENT PRIOR TO CONSTRUCTION COMMENCING.
- A COPY OF THE RETAINING WALL DESIGN DRAWINGS, INCLUDING CONNECTION OF AGGREGATE DRAINS TO THE STORMWATER DRAINAGE SYSTEM, DESIGN PARAMETERS AND CERTIFICATION BE PROVIDED TO THE SUPERINTENDENT AT THE PRE-START MEETING PRIOR TO CONSTRUCTION COMMENCING.
- ANY RETAINING WALL AND BATTER EXCEEDING THE HEIGHT OF 1.5m, THE CONTRACTOR SHALL UNDERTAKE A THIRD PARTY RPEQ REVIEW OF THE PROPOSED DESIGN.

RETAINING WALL DESIGN, CONSTRUCTION, SUPERVISION AND CERTIFICATION TO BE PROVIDED BY SPECIALIST SUB-CONTRACTOR.






PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD



COPYRIGHT (C) This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only

be used for the purpose for which they were intended. Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed. Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1


DRAWING TITLE

EARTHWORKS NOTES AND DETAILS

DEVEL. APPLIC. No.: -DATE: 24-04-24 PROJECT LEADER: JONATHAN CUELL **DESIGNER:** DRAFTSPERSON: CD FRASER LUCAS CHECKED: APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365 RPEQ No.: 21773

DATUM: AHD SCALE: AS NOTED FULL SIZE : A PROJECT No.: DRAWING No. VERSION: C220 BE230128-01A NOT FOR CONSTRUCTION OR TENDER

PRELIMINARY



PHASE 1 - SITE ESTABLISHMENT

- 1. ESTABLISH STABILISED ACCESS POINT, SITE OFFICES, AND PARKING AREAS (LOCATION TO BE CONFIRMED ON SITE).
- 2. DESIGNATE AND CORDON OFF ANY EXCLUSION AREAS (ANY AREAS OF THE SITE THAT ARE NOT TO BE ACCESSED).
- 3. INSTALL DUST FENCES ALONG ALL BOUNDARIES WITH EXISTING RESIDENTIAL DEVELOPMENT.
- 4. INSTALL SEDIMENT FENCES DOWNSLOPE FROM ALL DISTURBED AREAS AS INDICATED ON THE DRAWINGS (AS A MINIMUM).
- 5. INSTALL CLEAN WATER DIVERSION DRAINS WITH APPROPRIATE EROSION RESISTANT MATERIALS AND ROCK CHECK DAMS IN THE LOCATIONS INDICATED ON THE DRAWINGS.
- 6. CONSTRUCT TYPE B SEDIMENT BASINS PRIOR TO CARRYING OUT BROAD SCALE CLEARING IN THE SAME CATCHMENT.
- 7. INSTALL ALL DIRTY WATER DIVERSIONS AND TEMPORARY SEDIMENT TRAPS ENSURING DE-WATERING FACILITIES ARE AVAILABLE WHEN REQUIRED.
- 8. COMMENCE CLEARING WORK STARTING AT THE TOP OF EACH CATCHMENT IDEALLY CLEARING SHOULD BE CARRIED OUT PROGRESSIVELY WITH THE BULK EARTHWORKS TO LIMIT EROSION.
- 9. PROGRESSIVELY STRIP, STOCKPILE, AND SEED TOPSOIL WITH A FAST GROWING PASTURE MIX. ALL TOPSOILS MUST BE CARED FOR DURING CONSTRUCTION TO ENSURE SUCCESSFUL REVEGETATION.
- 10. COMMENCE BULK EARTHWORKS, ENSURING A MINIMAL AMOUNT OF AREA IS DISTURBED AT ANY ONE TIME.


PHASE 2 - CLEARING AND BULK EARTHWORKS

- 11. RESPREAD TOPSOIL OVER COMPLETED EARTHWORKS AND SOW WITH SUITABLE VEGETATIVE COVER AS SOON AS PRACTICABLE.
- 12. ONCE ALL EXPOSED AREAS HAVE BEEN STABILISED WITH TOPSOIL AND AT LEAST 80% VEGETATIVE COVER, ALL TEMPORARY SEDIMENT CONTROLS INCLUDING SEDIMENT BASINS MAY BE REMOVED AND THE BULK EARTHWORKS IN THOSE AREAS COMPLETED AND REVEGETATED.
- 13. REMOVE ALL TEMPORARY CLEAN WATER DIVERSION DRAINS AND REVEGETATE.
- 14. REMOVE SITE OFFICES AND DUST FENCING AND REVEGETATE ANY OTHER DISTURBED AREAS.
- 15. ENSURE ALL EXTERNAL ROADS HAVE BEEN SWEPT CLEAN AND ARE FREE OF ANY SEDIMENT.

SEDIMENT AND EROSION CONTROL CERTIFICATION

I, TOBY BENNETT HEREBY CERTIFY THAT THE SEDIMENT AND EROSION CONTROL MEASURES AND DEVICES SHOWN ON THIS DRAWING HAVE BEEN DESIGNED IN ACCORDANCE WITH THE 'BEST PRACTICE EROSION AND SEDIMENT CONTROL' (IECA AUSTRALASIA, NOVEMBER 2008).

SIGNED RPEQ No. 21912 DATED 05-09-2023



SEDIMENT BASIN TYPE B TYPICAL SECTION

TEMPORARY SEDIMENT BASIN CALCULATIONS MIN. SEDIMENT | MIN. SEDIMENT APPROX. REQ APPROX. LENGTH APPROX. WIDTH APPROX. DEPTH TIME LAB FLOC 0.5Q1 CATCH L:W D_S TOTAL VOLUM **BATTER** CONC. SETTLE MINIMUM A_S (m²) ACTUAL V_S (m³) STORAGE AT SPILLWAY STORAGE VOLUM SED STORAGE AT SPILLWAY SETTLE RATE AT SPILLWAY BASIN ID (mm/hr) (m^3/s) AREA (ha) TYPE RATIO AT SPILLWAY (m) 1 in X (mins) DEPTH (m) DEPTH (m) (m/hr) DEPTH (m) (m) (m) (m) 0.37 7.336 0.6 29 0.109 0.40 0.60 1309 785 0.2 236 0.2 69.9 23.3 8.0 1020.7

PRELIMINARY
NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCIL RFI UPDATES	24-04-24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08-12-23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.
Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE

EROSION &
SEDIMENT CONTROL
BASIN NOTES AND
DETAILS

DEVEL. APPLIC. No. :	-	DATE: 24-04-24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER :	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AND BURCHILLS ENGIN July	O ON BEHALF OF EERING SOLUTIONS	S ABN 76 166 942 365
U		111 20 110

SCALE: AS NOTEDDATUM: AHDFULL SIZE: A1PROJECT No.:DRAWING No.:VERSION:BE230128-01AC251B

EROSION AND SEDIMENT CONTROL NOTES


- THIS DRAWING HAS BEEN PREPARED AS A GUIDE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MANAGE SITE SEDIMENT AND EROSION CONTROL MEASURES AND DURING THE CONSTRUCTION PERIOD INSTALL ADDITIONAL MEASURES WHERE SCOUR OR SEDIMENT TRANSPORT IS LIKELY TO
- 2. DELAY CLEARING, GRUBBING AND TOPSOIL STRIPPING UNTIL NECESSARY.
- 3. COMMENCE WORK ON SITE ONLY AFTER SEDIMENT AND EROSION CONTROL MEASURES ARE IN PLACE.
- 4. MANAGE SITE ENTRY/EXIT POINTS TO ENSURE SEDIMENT IS NOT TRACKED OFF SITE.
- SHAKEDOWN AREA: PROVIDES FOR CONSTRUCTION, SERVICE AND STAFF VEHICLES ENTERING PUBLIC ROADS. CONTRACTOR SHALL LOCATE TO SUIT SITE ACTIVITIES. CONSTRUCTED AS 250mm THICK LAYER OF COARSE (150mm -200mm) RIVER GRAVEL OVER A SINGLE LAYER OF HIGH STRENGTH GEOTEXTILE (15m x 5m).
- 6. THE CONTRACTOR SHALL INSTALL EITHER STORMWATER INLET SEDIMENT TRAPS OR EXCAVATED INLET ARRANGEMENT AT ALL STORMWATER STRUCTURES DURING THE CONSTRUCTION.
- 7. FILTER ROLLS SHALL BE INSTALLED AT GULLY PITS IMMEDIATELY AFTER GULLY PIT CONSTRUCTION AND LEFT IN PLACE DURING THE MAINTENANCE PERIOD. OPERATION OF ROLLS DURING PERIODS OF HEAVY RAIN TO BE MONITORED TO PREVENT FLOODING AND EROSION DAMAGE ELSEWHERE.
- ARRANGE FOR EROSION CONTROL MEASURES TO BE INSTALLED AS CLOSE AS POSSIBLE TO THE SOURCE OF EROSION.
- ENSURE STOCKPILED TOPSOIL AND EARTHWORKS ARE NOT ERODED BY WIND AND STORMWATER RUN-OFF AND ARE PROVIDED WITH A SEDIMENT FENCE AROUND THE LOW SIDE.
- 10. SEDIMENT FENCES HAVE BEEN ESTABLISHED UNDER BULK EARTHWORKS CONTRACT, ERECT SEDIMENT FENCES IF REQUIRED. GENERALLY ALONG THE LOW SIDE OF THE CONSTRUCTION SITE AND ALONG A LINE OF CONSTANT LEVEL. AS AN ALTERNATIVE TO BURYING THE SEDIMENT FENCE LOWER EDGE, THE CONTRACTOR MAY ELECT TO PLACE 200mm OF THE FABRIC ON THE GROUND UP-SLOPE OF THE FENCE AND COVER WITH 100mm MIN LAYER OF AGGREGATE.
- 11. TO PREVENT EROSION, TOPSOIL AND SEED IMMEDIATELY AFTER COMPLETION OF BULK EARTHWORKS TO FINISHED PROFILES.
- 12. PROVIDE TURF STRIP ADJACENT TO KERB FOR FULL LENGTH OF NEW ROAD AND TURF STRIP PLACED AT 90° TO KERB EVERY 10m FOR FULL WIDTH OF VERGE.
- 13. PRIOR TO COMPLETION OF CONSTRUCTION OF PAVEMENT AND SEALING, PLACE SANDBAGS AT 45° TO ARREST SCOUR AGAINST KERB AND CHANNEL AS FOLLOWS:

ROAD GRADE 0.5% - 5% - 25m MAX CRS. 5% - 10% - 10m MAX CRS.

10% - 15% - 15m MAX CRS.


15% - 20% - 5m MAX CRS.

- 14. SWEEP EXTERNAL ROADS WHERE SEDIMENT HAS BEEN DROPPED FROM CONSTRUCTION VEHICLES. DO NOT WASH SEDIMENT INTO THE STORMWATER SYSTEM.
- 15. ALL SEDIMENT AND EROSION CONTROL STRUCTURES, TRENCHES ETC. SHALL BE REGULARLY MAINTAINED AND INSPECTED FOR EFFECTIVENESS.
- THE USE OF POTABLE WATER IS NOT PERMITTED IN SITE EARTHWORKS OPERATIONS, ROAD AND PAVEMENT CONSTRUCTION OR DUST SUPPRESSION. RECYCLED WATER IS REQUIRED TO BE USED AND IS TO BE IN ACCORDANCE WITH L.C.C GUIDELINES.



NOTE: SEDIMENT FENCE TO HAVE TURNOUTS AT 50m MAX INTERVALS.


REFER TO IPWEAQ STANDARD DRAWINGS D-0040 AND D-0041 FOR ALL ADDITIONAL SEDIMENT CONTROL DETAILS




TYPICAL STOCKPILE CONFIGURATION

N.T.S.

1. LOCATE STOCKPILES AT TOP OF CATCHMENT ON FLAT GROUND AND NOT WITHIN 5m OF CONCENTRATED FLOW PATHS. STOCKPILES SHOULD HAVE EARTHBANKS UPSLOPE FOR DIVERSION OF UPSTREAM WATER AROUND STOCKPILE AND SEDIMENT FENCES PLACED 1-2m DOWNSLOPE.





ROCK CHECK DAM TYPICAL CROSS SECTION N.T.S.



DUST CONTROL FENCE

DUST CONTROL FENCE TO BE PLACED AS DIRECTED ON-SITE BY SUPERINTENDENT.





N.T.S.

LONGITUDINAL SECTION

PRELIMINARY

NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCIL RFI UPDATES	24-04-24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08-12-23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended. Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed. Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE

EROSION & SEDIMENT CONTROL TYPICAL NOTES AND **DETAILS**

DEVEL. APPLIC. No.: -DATE: 24-04-24 PROJECT LEADER: JONATHAN CUELL DESIGNER: DRAFTSPERSON: CD CHECKED: FRASER LUCAS APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

RPEQ No.: 21773 DATUM: AHD FULL SIZE : A SCALE: AS NOTED PROJECT No.: DRAWING No.: VERSION:

BE230128-01A

C252

SEDIMENT AND EROSION CONTROL CERTIFICATION

HEREBY CERTIFY THAT THE SEDIMENT AND EROSION CONTROL MEASURES AND DEVICES SHOWN ON THIS DRAWING HAVE BEEN DESIGNED IN ACCORDANCE WITH THE 'BEST PRACTICE EROSION AND SEDIMENT CONTROL' (IECA AUSTRALASIA, NOVEMBER 2008).

SIGNED RPEQ No. DATED ..

REFER TO IPWEAQ STANDARD DRAWINGS D-0040 AND D-0041 FOR ALL ADDITIONAL SEDIMENT CONTROL DETAILS.

	QMS RISK & OPPORTUNITIES REGISTER SAFETY IN DESIGN – NORMAL DESIGN RISKS - CIVIL						
Design Element	Associated risks & opportunities	Raw risk assessment		Raw risk rating	Treatment Measures to avoid, minimize or treat the risk.	Responsibility	Residual risk rating
CONSTRUCTION BUASE		Like	Con				
CONSTRUCTION PHASE							
SITE ACCESS	Unsafe site access and egress point, restricted access, flooding, unauthorised access from persons or animals	L	M	L-M	Prepare site specific Construction Traffic Management Plan and Workplace Health and Safety Management Plan	Principal Contractor	L
CLEARING & DEMOLITION	Removal of existing structures, decommision of services, vegetation clearing and fauna management	М	Н	М-Н	Contractor to obtain Demolition Permit, arrange all service disconnections with asset ownerand carry out vegetation works in accordance with Vegetation and Fauna Management Plan	Principal Contractor	L
EXISTING SERVICES	Distrub or damage existing services and infrastructure, overhead powerlines, work adjacent to existing services, existing service relocations	М	Н	М-Н	Client to commission detailed site survey and service potholing at critical locations. Contractor to undertake Dial Before You Dig and service verification with service authoritiy providers and undertake additional potholing prior to construction	Client and Principal Contractor	L-M
EXCAVATION & TRENCHING	Unstable existing slopes and landslip, steep cut profiles, deep trench excavations, working at heights, intercept water table, dispersive soils, acid sulphate soils	М	Н	М-Н	Client to commission a geotechnical investigation and contractors to undertake own investigations. Temporary and final earthworks profiles confirmed by client's geotechnical consultant. Tempory earthworks profile to be confirmed by Contractor's geotechnical consultant. Contractor to provide temporary benching, fencing, stabilisation and shoring.	Client and Principal Contractor	L
MATERIALS HANDLING	Manual handling, handling and disposal of sharps, repeative work processeds, hazardous substances	н	М	М-Н	Contractor or provide a site specific Workplace Health and Safety Management Plan including Material Safety Data Sheets	Principal Contractor	L
PLANT & EQUIPMENT	Operation of plant and machinery, site access by visitors, material deliveries and waste removal	М	Н	М-Н	Contractor or provide a site specific Workplace Health and Safety Management Plan including register of operator machinery tickets. Contractor to maintain a site visitor register and provide site specific induction to all visitors	Principal Contractor	L
OPERATIONAL PHASE							
ROADS & PATHWAYS	General road safety, flood free access, pedestrian and cyclist injuries, inadequate signage	L	Н	М	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
STORWATER / FLOODING	Hazard from storm and flood water depths and velocities, ponding and access to inlets, outlets and basins	М	Н	М-Н	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
WATER & SEWER	Blockages, contamination, interuption to service, access to fittings, confined space access	L	М	L-M	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
WALLS & FENCING	Risk of falls, unauthoried access from persons and animals, structural failure	М	M	М	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
MAINTENANCE PHASE							
ROADS & PATHWAYS	All as for construction and operation phases					Asset Owner	
STORWATER / FLOODING	All as for construction and operation phases					Asset Owner	
WATER & SEWER	All as for construction and operation phases					Asset Owner	
WALLS & FENCING	All as for construction and operation phases					Asset Owner	
REFURBISHMENT PHASE							
ROADS & PATHWAYS	All as for construction and operation phases					Asset Owner	
STORWATER / FLOODING	All as for construction and operation phases					Asset Owner	
WATER & SEWER	All as for construction and operation phases					Asset Owner	
WALLS & FENCING	All as for construction and operation phases					Asset Owner	
DEMOLITION PHASE							
ROADS & PATHWAYS	All as for construction and operation phases					Asset Owner	
STORWATER / FLOODING	All as for construction and operation phases					Asset Owner	
WATER & SEWER	All as for construction and operation phases					Asset Owner	
WALLS & FENCING	All as for construction and operation phases					Asset Owner	

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

A 1 ORIGINAL SIZE BEFORE REDUCTION COUNCIL RFI UPDATES 24-04-24 PRELIMINARY CIVIL ENGINEERING DESIGN 08-12-23 VER. DESCRIPTION DATE

COPYRIGHT C

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE:

HAZARD RISK REGISTER -**DESIGN RISKS**

DEVEL. APPLIC. No.: -DATE: 24-04-24 PROJECT LEADER: JONATHAN CUELL DESIGNER: DRAFTSPERSON: CD FRASER LUCAS CHECKED: APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

RPEQ No.: 21773 SCALE: AS NOTED DATUM : AHD FULL SIZE : A1

PROJECT No.: DRAWING No.: VERSION: BE230128-01A C900

The experience **you deserve** \geqslant



Our Ref: BE230128-MEM-HIA-Stg1-02.docx

Enquiries: Melissa Blum

TECHNICAL MEMORANDUM

Date	26/04/2024
То	Lowood One Pty Ltd
From	Melissa Blum
Project	BE230128 – 2983 Forest Hill Fernvale Road, Lowood
Subject	Conceptual Stormwater Management Plan – Stage 1

1. BACKGROUND

Lowood One Pty Ltd have engaged Burchills Engineering Solutions to prepare a Conceptual Stormwater Management Plan (CSMP) to accompany a Development Application to be submitted to Somerset Regional Council (the 'Council' or 'SRC'). The Application sought is a Reconfiguring a Lot Approval for Stage 1 of the development which includes 48 lots, including 4 duplex allotments.

The properties included in this Development Application include:

- Lot 56 Forest Hill Fernvale Road, Lowood (Lot 56 on SP 197415); and
- Lot 57 Forest Hill Fernvale Road, Lowood (Lot 57 on SP 197415).

This report has been prepared to address the requirements of the Somerset Region Planning Scheme, Version 4.2 (2016).

This report should be read in conjunction with the Hydraulic Impact Assessment (BE230128-TM-HIA-Stg1-02.pdf) and the Master Stormwater Management Plan (MSMP) (BE230128-RP-MSMP - 02.pdf).

1.1 Information Request Response

This CSMP revision has been prepared to address Somerset Regional Council Information Request dated 23 February 2024. The relevant items and associated responses have been included in the following table.



Table 1.1 Information Request Response

Item No.	Table 1.1 Information Re	Response
17	Attachment B- Stormwater Civil Hydraulic Engineering Report section 5.1 refers to package BE230128-01A for detailed erosion and sediment control design drawings. Please provide Package BE230128-01A for assessment?	Drawing Package BE230128-01A has been included in Appendix E.
18	Attachment B – Stormwater Civil Hydraulic Engineering Report – Appendix C – Burchills Civil Engineering Drawings differ from the submitted Attachment G – Operational Works Plans. Please clarify the differences and reason for these differences?	Plans have been updated to ensure consistency.
19	Attachment B – Stormwater Civil Hydraulic Engineering Report – Appendix C – Burchills Civil Engineering Drawings – SK201 - Earthwork Sections – the lots shown on sections A and B do not correspond to the lots at section locations shown, please clarify?	Plans have been updated to ensure consistency.
20	Attachment B – Stormwater Civil Hydraulic Engineering Report – Appendix C – Burchills Civil Engineering Drawings – SK301 – Typical Road Cross Sections – do not provide a typical section for Road 4. Please provide section for Road 4.	Section for Road 4 has been included
21	Attachment B – Stormwater Civil Hydraulic Engineering Report – Appendix C – Burchills Civil Engineering Drawings do not provide any detailed erosion and sediment control plans for Stage 1. Please provide detailed erosion and sediment control plans for Stage 1.	Drawing and sediment control plan for Stage 1 has been included in Appendix E.
22	Attachment B – Stormwater Civil Hydraulic Engineering Report does not provide any stormwater sizing calculation for the stormwater network. Please provide calculations.	The stormwater calculations will be completed at OPW.
23	Attachment B – Stormwater Civil Hydraulic Engineering Report – Burchills Stage 1 Civil Engineering Report Appendix B – Civil Drawings show stage 1 operational works drawings which differ from the plans submitted in Appendix G and also differ from the Burchill Civil Engineering Drawings contain in Appendix C of Attachment B. Please clarify why so many differing Operational Works drawing exist and which set is to be assessed?	Plans have been updated.
24	Attachment B – Stormwater Civil Hydraulic Engineering Report – Burchills Stage 1 Civil Engineering Report Appendix B – Civil Drawings C220 detail sleeper retaining wall but no sleeper wall are shown to be provided on the layout drawings or typical sections. Please clarify the provision of this detail and the location of any retaining wall to be provided?	Plans have been updated.





Item No.	Item	Response		
25	Attachment B – Stormwater Civil Hydraulic Engineering Report contains Burchills Stage 1 Civil Engineering Report December 2023 and Burchills Civil Engineering Report December 2023.	Plans have been updated.		
	Please clarify which is provided for assessment.			
26	It is noted that the waterway through the site is 'low' (green) waterway on the Queensland waterways for waterway barrier works mapping. Please clarify that the operational works design has considered requirements for waterway barrier works, including all proposed structures and culverts.	The OPW design has considered the requirements for waterway barrier works, including: • Culverts within the waterway have a minimum culver aperture width of 1.2m and will be placed within the low flow channel. • Culverts will be installed at or below bed level, • Culvert cells will be aligned parallel to the direction of water flow to minimise turbulence.		

2. SITE DETAILS

The subject site is located at 2983 Forest Hill Fernvale Road, Lowood, QLD and can be formally described as Lot 56 and 57 SP 197415 with a total area of 41.68ha. Refer to Figure 2.1 for the site locality.



Figure 2.1 Site Locality (QLD Globe, 2023)

2.1 Proposed Development

The proposed Stage 1 development includes 48 lots, including 4 duplex allotments, as shown in Figure 2.2. These lots will be filled above the Design Flood Level (1% AEP plus 300mm freeboard).



The experience you deserve



Figure 2.2 Proposed Stage 1 Development (Burchills, 2024)





4. STORMWATER QUALITY MANAGEMENT PLAN

4.1 Water Quality Objective (WQO)

In accordance with the Somerset Region Planning Scheme (Version 4.2) and the SEQ Water 'Water Quality Management in Drinking Water Catchments Development Guidelines' (2017), the total effect of permanent water quality control measures are to achieve reductions in the mean annual load generated by the development site at a minimum of:

- 85% for Total Suspended solids (TSS);
- 65% for Total Phosphorus (TP);
- 45% for Total Nitrogen (TN);
- 95% for Gross Pollutants (>5mm); and

This will ensure the environmental values of the downstream receiving waters are maintained and have been chosen as the WQO for the development.

4.2 Treatment Train

4.2.1 Overall

To ensure the above WQO's can be met at each of the site's LPDs, a treatment train was proposed for the developed site and modelled using the Model for Urban Stormwater Improvement Conceptualisation (MUSIC) software.

It is proposed to use bioretention basins.

4.2.2 Bioretention Basin

The parameters of the proposed bioretention basins are presented in Table 4.1. The location of the proposed treatment train elements are shown in Figure 4.1.

Table 4.1 Proposed Bio-retention Basin Parameters

Basin ID	Parameter	Modelled Value
	Filter area	900m²*
	Extended detention depth	0.3m
Stage 1	Filter media depth	0.4m
	Transition Layer	0.10m
	Drainage Layer	0.2m

^{*} Bioretention Basin for Stage 1 is greater than 800m² and needs to split into two cells, TBC at detailed design phase.






Figure 4.1 Stage 1 MUSIC Catchment Plan

Typical sections of a bioretention basin have been included in Figure 4.2 and Figure 4.3. The bioretention systems will be designed in accordance with the Water by Design Technical Guidelines (Water by Design, 2014) during the detailed design phase of the development.




Figure 4.2 Typical Bioretention Basin (Water By Design, 2014)






Figure 4.3 Typical Bioretention Drainage Profile (Water By Design, 2014)

4.3 MUSIC Results - Stage 1

Results of the MUSIC modelling for the treatment train effectiveness for the Stage 1 are summarised in Table 4.2. The results indicate the WQO are achieved for the rainfall data set simulated.

Table 4.2 Stage 1 Treatment Train Effectiveness

Pollutant	Inflows (kg/yr)	Outflows (kg/yr)	Reduction Achieved (%)	Water Quality Objective (%)
TSS	9,480	685	92.8	80
TP	17.1	2.42	85.8	60
TN	75.8	32.5	57.2	45
GP	921	0	100	90

NOTE: All simulations have been run with pollutant export estimation set to 'stochastic generation'.

A screen capture of the MUSIC model and treatment train effectiveness results is presented in Figure 4.4.



The experience you deserve




Figure 4.4 Stage 1 Treatment Train Layout & MUSIC Results

5. EROSION AND SEDIMENT CONTROL PLAN

5.1 Best Management Practices

Stormwater runoff quality during the construction phase of this development shall be managed in accordance with Best Practice Erosion and Sediment Control (IECA, 2008), which is the current recognised construction industry best management practice (BMP) for erosion and sediment control.

Erosion and Sediment Control (ESC) plans are required to be implemented during the construction phase to minimise environmental harm to on-site stormwater treatment devices and downstream receiving waters.

Detailed Erosion and Sediment Control design drawings have been prepared submitted as part of the Bulk Earthworks Operational Works Application submitted concurrently with this ROL Application. Please refer to Drawing Package No. BE230128-01A prepared by Burchills Engineering Solutions for further detail (Appendix E).

5.2 Erosion Hazard Assessment

As part of the IECA guidelines, an erosion hazard assessment is completed to identify low-risk and high-risk short-term land disturbances within a given region (IECA, 2008). This Erosion Hazard Assessment estimates a TASK number which triggers if a site should be treated as high or low risk in regard to erosion control measures. A trigger value for high-risk site of 200 has been adopted in this CSMP as recommended by IECA. Table 5.1 below show the values used for the estimation of the TASK number.

Catchment
IDArea (m²)Duration of
Disturbance (months)Slope FactorK FactorTASK NumberStage 1730060.210.4404047.1

Table 5.1 Erosion Hazard Assessment

From Table 5.1 the results show that the internal catchment requires high-risk ESC treatment. Given the development proposal is at a conceptual phase, further details of the erosion and sediment control systems and procedures will be provided at the detailed design stage.

5.3 Erosion Control Standard

The best practice erosion control measures for high-risk development as detailed in Best Practice Erosion and Sediment Control (IECA, 2008) include the following:

- All reasonable and practical steps to be taken to apply best practice erosion control
 measures to completed earthworks, or otherwise stabilise such works, prior to anticipated
 rainfall including existing unstable, undisturbed, soil surfaces under the management or
 control of the building/construction works;
- Land clearing limited to maximum 4 weeks work;
- Disturbed soil surfaces stabilised with minimum 75% cover within 10 days of completion of works within any area of a work site;
- Staged construction and stabilisation of earth batters; and
- Soil stockpiles and unfinished earthworks are suitably stabilised (covered) if disturbance is expected to be suspended for a period exceeding 10 days.



5.4 Sediment Loss Estimate

As the site has been classified as high-risk, a sediment loss estimate has been included to indicate the recommended sediment control techniques.

The potential volume of sediment loss from the subject site has been estimated using the Revised Universal Soil Loss Equation (RUSLE).

RUSLE calculates annual soil loss rates based on:

A = R. K. LS. C.P

Where:

A = annual soil loss due to erosion (t/ha/yr)

R = rainfall erosivity factor

K = soil erodibility factor

LS = topographic factor derived from slope length and slope gradient

C = cover and management factor

P = erosion control practice factor

Table 5.2 Potential Sediment Loss (RUSLE)

Catch.	Area (ha)	Soil Type*	Slope length (m)	Slope Grade (%)	Intensity ⁶ I ₂ (mm/hr)	R	К	LS	С	Р	A (t/ha/yr)	Yeild (m³/yr)
Stage 1	7.3	Sandy Clay	100	1.00	9.4	1987	0.025	0.24	1	1.3	15.5	87.0

^{*}Note soil testing will need to be carried out to confirm soil type.

5.5 Sediment Control Standard

Table B1 of the guidelines (IECA, 2018) provides a method for determining the sediment control standard for construction activities based on the estimated soil loss rate. Based on the estimated soil loss rates and the size of the contributing catchment, Type 3 sediment controls are required for this site as a minimum. A list of Type 3 and supplementary sediment control techniques is provided in Table 5.3 based on Table 4.5.3 and Table 4.5.4 of the guidelines (IECA, 2008). These control techniques provide a guide that is recommended to be used to minimise the downstream effect of sediments.

Table 5.3 Sediment Control techniques

Techniques	Type 3	Supplementary						
	Buffer Zone	Grass Filter Strips						
	Fabric Drop Inlet Protection	Fibre Rolls						
Sheet flow treatment	Filter Fence							
	Straw Bale Barrier							
	Sediment Fence							





Techniques	Type 3	Supplementary
Concentrated flow treatment	Coarse Sediment Trap	 Straw Bale Barrier Kerb Inlet Sediment Traps (on-grade and sag inlet traps, including Gully Bags)
De-watering sediment control	Sediment Fence	Grass Filter bed
Instream sediment control	Modular Sediment Barrier	Straw Bale Barrier (short-term device only)
Other		Construction exits (Rock Pads, Wash Bays)





6. CONCLUSION

This CSMP for Stage 1 has been prepared for Lowood One Pty Ltd to accompany the Development Application to allow for the development of 48 lots, including 4 duplex allotments on 2983 Forest Hill Fernvale Road, Lowood.

The CSMP has referenced relevant guidelines relating to stormwater management to form the conceptual basis of the stormwater plan. The following conclusions have been made as result of the study.

Stormwater Quality

The stormwater quality on-site is proposed to be managed through a bioretention basin, with a total filter area of 900m². This basin achieves the Water Quality Objectives, in line with the Somerset Region Planning Scheme (Version 4.2) and the SEQ Water 'Water Quality Management in Drinking Water Catchments Development Guidelines' (2017).

Construction Management for Erosion and Sediment

Detailed Erosion and Sediment Control design drawings have been prepared submitted as part of the Bulk Earthworks Operational Works Application submitted concurrently with this ROL Application. Please refer to Drawing Package No. BE230128-01A prepared by Burchills Engineering Solutions for further detail.

Yours sincerely,

Melissa Blum

Senior Water Engineer

Melklum

Samuel Huddy

Senior Water Engineer

RPEQ - 29555






Appendix A – Proposed Plans of Development







Prepared for: LOWOOD ONE PTY LTD

Designer: TG
Checked: CD
Date: 24.03.24

STAGE 1 - SUBDIVISION LAYOUT
CONCEPT CIVIL DRAWINGS

SCALE 15 0 15 30 45 60 75 (metres)
1:1500 (FULL SIZE) (metres)

BE230128-01-SK010-B



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +617 7 5509 6411 Emaii: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365



Appendix B - MUSIC Input Parameters

Rainfall and Evapotranspiration Parameters

MUSIC modelling was based on 6-minute interval data obtained from the Bureau of Meteorology (BOM) for rainfall station 40584 HINZE, as summarised in Table D.6-1.

Table D.6-1 Meteorological and Rainfall Runoff Data Reporting Table

Input	Data Used in Modelling
Rainfall station	Wivenhoe
Time step	6 minute
Modelling period	1-01-1976 to 31-12-1985 (10 years)
Mean annual rainfall (mm)	1371
Evapotranspiration	1445
Rainfall runoff parameters	Residential
Pollutant export parameters	Residential

Catchment Parameters

Based on the proposed land uses within the development, the subject site has been modelled as tbc in Table D.6-2. The site has been divided into roof and ground level source nodes as per the architectural drawings included in Appendix A.

Table D.6-2 Land Use Parameters

Stage	Area (ha)	Land use	Total Impervious (%)
Post-STG-1A Landscape	0.223	Park	10
Post-STG-1A Lot-Roof	1.125	Roof	100
Post-STG-1A Lot-Ground	1.688	Ground	60
Post-STG-1A Road	2.336	Road	90
Post-STG-1B Landscape	1.106	Park	10
Post-STG-1B Landscape	0.830	Park	10

The MUSIC catchment plan with full breakdown of roof and ground areas is presented in Appendix E. The pollutant loads and runoff parameters for each source node have been based on the data from the Water by Design MUSIC Modelling Guidelines (Water By Design, 2010), as summarised in Table D.6-3 and Table D.6-4.





Table D.6-3 Rainfall Runoff Parameters Urban

Parameter	All Nodes
Landuse	Residential
Rainfall threshold (mm)	1
Soil storage capacity (mm)	500
Initial storage (% capacity)	10
Field capacity (mm)	200
Infiltration capacity coefficient a	211
Infiltration capacity exponent b	5
Initial depth (mm)	50
Daily recharge rate (%)	28
Daily baseflow rate (%)	27
Daily deep seepage rate (%)	0

Table D.6-4 Pollutant Load Parameters

Urban	Total Suspended Solids (log mg/L)		Total Phosphorous (log mg/L)		Total Nitrogen (log mg/L)	
Residential	Mean	Std Dev.	Mean	Std Dev.	Mean	Std Dev.
Storm Flow Concentration	1.30 ⁽¹⁾ 2.43 ⁽²⁾ 2.18 ⁽³⁾	0.39	-0.89 ⁽¹⁾ -0.30 ⁽²⁾ -0.47 ⁽³⁾	0.31	0.26	0.23
Base Flow Concentration	0 ⁽¹⁾ 1 ^(2,3)	0 ⁽¹⁾ 0.34 ^(2,3)	0 ⁽¹⁾ -0.97 ^(2,3)	0 ⁽¹⁾ 0.31	0 ⁽¹⁾ 0.20 ^(2,3)	0 ⁽¹⁾ 0.20 ^(2,3)

NOTE: (1) Values applied to "Roof" areas

(2) Values applied to "Road" areas

(3) Values applied to "Ground" areas



Treatment Node Parameters

The following sections describe the modelling parameters applied to MUSIC for each of the treatment nodes included as part of the water quality assessment.

Bioretention System

The input parameters for the bioretention system are summarised in Table D.6-5.a

Table D.6-5 Bioretention Parameters


Table D.0-3 Bioretention Farame	
ID	С
Surface area (m2)	900
Has the filter area been calculated appropriately? (Y / N / N/A)	Y
Extended detention depth (m)	0.3
Filter area (m²)	900
Unlined filter media perimeter (m)	139
Saturated hydraulic conductivity (mm/hour)	200
Filter depth (m)	0.4
TN content of filter media (mg/kg)	400
Orthophosphate content of filter media (mg/kg)	30
Is the base lined? (Y/N)	Yes
Effectiveness of plant TN removal (effective/ineffective/unvegetated)	Effective
Overflow weir width (m)	95
Exfiltration rate (mm/hr)	0
If an exfiltration rate has been used, have node water balance losses been used in calculation of treatment train effectiveness? (Y / N / N/A)	N/A
If exfiltration rate has been used, is the exfiltration rate justified? (Y / N / N/A)	N/A
Underdrain present? (Y/N)	Yes
Submerged zone with carbon present?	No
Depth of submerged zone (m)	N/A
Confirmation that K and C* remain default? (Y/N)	Yes







Appendix C – Burchills Stormwater Drawings












Appendix D – Burchills Civil Engineering Drawings - Concept Civil Engineering Stage 1

PROPOSED LAND SUBDIVISION AT 2983 FOREST HILL FERNVALE RD, LOWOOD QUEENSLAND 4311

CONCEPT CIVIL ENGINEERING STAGE 1

CONTRACT BE230128-01



DRAWING INDEX			
DWG No.	DESCRIPTION		
SK000	COVER SHEET		
SK200	BULK EARTHWORKS LAYOUT PLAN		
SK201	EARTHWORKS SECTIONS		
SK300	ROADWORKS AND DRAINAGE LAYOUT PLAN		
SK301	TYPICAL ROAD CROSS SECTIONS		
SK310	ROAD 1 LONGITUDINAL SECTIONS		
SK311	ROADS 4 & 5 LONGITUDINAL SECTIONS		
SK312	ROADS 6 & 7 LONGITUDINAL SECTIONS		
SK313	ROAD 8 LONGITUDINAL SECTIONS		
SK320	BIO-RETENTION BASIN DETAIL PLAN		
SK321	BIO-RETENTION BASIN DETAILS		
SK350	INTERSECTION FUNCTION LAYOUT PLAN		
SK500	CONCEPT WATER AND SEWER LAYOUT PLAN		

PREPARED FOR

LOWOOD ONE PTY LTD





GOLD COAST | BRISBANE | TOOWOOMBA
IPSWICH | MORETON BAY
PHONE: +61 7 5509 6400
FAX: +61 7 5509 6411
EMAIL: ADMIN@BURCHILLS.COM.AU
COOTE BURCHILLS ENGINEERING PTY LTD
ABN 76 166 942 365

NOTE:

DESIGNS HAVE BEEN UNDERTAKEN USING SURVEY DATA PROVIDED BY ONE SURVEYORS DATED 6 NOVEMBER 2023

PROJECT No.: DRAWING No. : VERSION: BE230128-01 SK000 B





PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

ORIGINAL SIZE BEFORE REDUCTION 24.04.24 PRELIMINARY CIVIL ENGINEERING DESIGN 08.12.23 DATE

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.





CONCEPT CIVIL ENGINEERING


EARTHWORKS SECTIONS

DATE: 24.04.24

DATUM : AHD DRAWING No.: VERSION:







PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

A 1 ORIGINAL SIZE BEFORE REDUCTION COUNCILL RFI UPDATES 24.04.24 PRELIMINARY CIVIL ENGINEERING DESIGN 08.12.23 DESCRIPTION DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE:

TYPICAL ROAD **CROSS SECTIONS**


DEVEL. APPLIC. No.: -DATE: 24.04.24 PROJECT LEADER: JONATHAN CUELL DESIGNER: DRAFTSPERSON: CD CHECKED: FRASER LUCAS APPROVED FOR AND ON BEHALF OF

BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

VERSION:

SCALE: AS NOTED DATUM : AHD PROJECT No.: DRAWING No.: BE230128-01 SK301

PRELIMINARY NOT FOR CONSTRUCTION OR TENDER



PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROAD 1 LONGITUDINAL SECTIONS

DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER :	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AN	D ON BEHALE OF	

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

RPEQ No. :

SCALE: AS NOTEDDATUM: AHDFULL SIZE: A1PROJECT No.:DRAWING No.:VERSION:BE230128-01SK310B


VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres) (FULL SIZE)

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD



COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER
This drawing and its con

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROADS 4 & 5 LONGITUDINAL SECTIONS

DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER:	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AN	D ON BEHALF OF	

BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

RPEQ No. :

PROJECT No.:

BE230128-01


DATUM: AHD

FULL SIZE: A

VERSION:

BK311

B



HORIZONTAL GEOMETRY

-0.6%

15mVC R = 625

-1.25

58.299

59.55 59.49

58 58

SAG TP (

20mVC R = 1666.67

0.24 0.13 0.12 0.15

57.610 57.581 57.580 57.610 57.663

57.37 57.44 57.45 57.49 57.52 0.44

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)

ROAD 4 LONGITUDINAL SECTION

EXISTING SURFACE \(\square\)

VERTICAL GRADE (%)

DATUM RL 51.0

LEVEL

LEVEL

VERTICAL CURVE LENGTH (m)

VERTICAL CURVE RADIUS (m)

DEPTH OF CUT (-ve)

HEIGHT OF FILL (+ve)

FINISHED SURFACE

EXISTING SURFACE

CONTROL LINE

CHAINAGE

....

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)

ROAD 5 LONGITUDINAL SECTION

PRELIMINARY
NOT FOR CONSTRUCTION OR TENDER

EXISTING SURFACE ~ SAG L DESIGN SURFACE TO STATE 1.3\$5% VERTICAL GRADE (%) 15mVC R = 346.02 15mVC R = 900.88 VERTICAL CURVE LENGTH (m) VERTICAL CURVE RADIUS (m) DATUM RL 49.0 DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve) FINISHED SURFACE 55.235 55.057 55.450 55.453 55.776 55.932 55.971 54.921 54.932 LEVEL EXISTING SURFACE 56.15 56.15 56.15 56.15 56.15 LEVEL 56. CONTROL LINE CHAINAGE


HORIZONTAL GEOMETRY

ROAD 6 LONGITUDINAL SECTION

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)



HORIZONTAL GEOMETRY

HORIZONTAL GEOMETRY

ROAD 7 LONGITUDINAL SECTION

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)

PRELIMINARY

NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER.	DESCRIPTION	DATE

COPYRIGHT C

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROADS 6 & 7 LONGITUDINAL SECTIONS

DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER:	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AN	D ON BEHALF OF	

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

____.

SCALE: AS NOTED

DATUM: AHD

FULL SIZE: A1

PROJECT No.:

DRAWING No.:

VERSION:

BE230128-01

SK312

B

┌ DESIGN SURFACE 1 IN 4 TEMPORARY BATTER -1 IN 4 TEMPORARY BATTER FUTURE SURFACE \ - CULVERT GROUP 2 7x2100x600 RCBCs -0.6% 0.633% VERTICAL GRADE (%) $= \frac{30\text{mVC}}{\text{R} = 2433.1} =$ VERTICAL CURVE LENGTH (m) 30mVCR = 2481.71 VERTICAL CURVE RADIUS (m) DATUM RL 47.0 DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve) 0.41 FINISHED SURFACE 54.923 54.941 54.976 54.428 LEVEL EXISTING SURFACE 54.96 54.98 55.03 54.42 54.41 54.01 54.45 54.35 53.68 LEVEL 54. 53 22, 22, CONTROL LINE 291.815 CHAINAGE

ROAD 8 LONGITUDINAL SECTION

VERTICAL SCALE 2 0 2 4 6 8 10 1:200 (meters)

HORIZONTAL SCALE 20 0 20 40 60 80 100 1:2000 (meters) (FULL SIZE)

HORIZONTAL GEOMETRY

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER.	DESCRIPTION	DATE
	Α	B COUNCILL RFI UPDATES A PRELIMINARY CIVIL ENGINEERING DESIGN

COPYRIGHT C

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.
Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROAD 8 LONGITUDINAL SECTIONS

DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER:	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
ADDDOVED FOR AND ON DELIALE OF		


APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365


RPEQ No. :

PRELIMINARY


NOT FOR CONSTRUCTION OR TENDER

SCALE: AS NOTEDDATUM: AHDFULL SIZE: A1PROJECT No.:DRAWING No.:VERSION:BE230128-01SK313B










INTERSECTION FUNCTION LAYOUT PLAN

SCALE 5 0 5 10 15 20 25 (metres)

LEGEND



PRELIMINARY NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

ORIGINAL SIZE BEFORE REDUCTION COUNCILL RFI UPDATES 24.04.24 PRELIMINARY CIVIL ENGINEERING DESIGN 08.12.23 DESCRIPTION DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.
Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:


CONCEPT CIVIL ENGINEERING

DRAWING TITLE:

INTERSECTION FUNCTION LAYOUT PLAN

DEVEL. APPLIC. No.: -DATE: 24.04.24 PROJECT LEADER: JONATHAN CUELL DESIGNER: DRAFTSPERSON: CD CHECKED: FRASER LUCAS APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

SCALE: AS NOTED DATUM : AHD PROJECT No.: DRAWING No.: VERSION: BE230128-01 SK350





Appendix E – Burchills Civil Engineering Drawings – Earthworks OPW – Stage 1

PROPOSED RESIDENTIAL DEVELOPMENT AT 2983 FOREST HILL FERNVALE RD, LOWOOD QUEENSLAND 4311

EARTHWORKS OPW - STAGE 1

CONTRACT BE230128-01A

LOCALITY PLAN

DRAWING INDEX DWG No. DESCRIPTION **COVER SHEET** BULK EARTHWORKS LAYOUT PLAN EARTHWORKS SECTIONS EARTHWORKS NOTES AND DETAILS **EROSION & SEDIMENT CONTROL PLAN - EARTHWORKS PHASE EROSION & SEDIMENT CONTROL BASIN NOTES AND DETAILS EROSION & SEDIMENT CONTROL TYPICAL NOTES AND DETAILS** HAZARD RISK REGISTER - DESIGN RISKS

GENERAL NOTES:

ALL DRAWINGS UNDER THIS CONTRACT ARE TO BE READ IN CONJUNCTION WITH THE PROJECT SPECIFICATION

CONTROL SURVEY INFORMATION WILL BE ESTABLISHED ON SITE BY THE PRINCIPAL'S SURVEYOR. SETOUT

ON THE SITE WITHOUT WRITTEN AUTHORISATION FROM THE SUPERINTENDENT

ALL TOPSOIL STRIPPED FROM WORK AREAS SHALL BE STOCKPILED FOR LATER RE-SPREADING TO ALL FOOTPATHS, BATTERS AND ALLOTMENTS.

10. EARTHWORKS (GENERAL)

ALL FILL MATERIAL PLACED SHALL BE COMPACTED AND TRIMMED TO FINAL EARTHWORKS LEVELS AND PROFILES SHOWN ON THE CONTRACT DRAWINGS AND TESTED IN ACCORDANCE WITH THE PROJECT

ALL COMPACTION TESTING UNDER THIS CONTRACT IS TO BE CARRIED OUT TO AS3798 LEVEL 1 STANDARD BY A NATA-ACCREDITED TESTING AUTHORITY. CERTIFICATION FOR ALL EARTHWORKS CONSTRUCTION AND TESTING IS TO BE PROVIDED BY A REGISTERED PROFESSIONAL ENGINEER QUEENSLAND (RPEQ) ENGAGED BY THE CONTRACTOR.

11. COMPACTION STANDARDS

ALL FILL MATERIAL PLACED UNDER THIS CONTRACT SHALL BE COMPACTED IN ACCORDANCE WITH THE PROJECT SPECIFICATION AND CURRENT COUNCIL STANDARDS.

ALL TESTING SHALL BE CARRIED OUT BY AN APPROVED N.A.T.A. TESTING AUTHORITY IN ACCORDANCE WITH THE PROJECT SPECIFICATION AND COUNCIL STANDARDS.

13. "AS CONSTRUCTED" SURVEY

"AS CONSTRUCTED" SURVEY SHALL BE CARRIED OUT BY THE PRINCIPAL'S SURVEYOR AS WORK PROCEEDS. 14. MAINTENANCE OF SITE CONDITION

AT THE COMPLETION OF WORKS THE SITE IS TO BE LEFT IN A CLEAN AND TIDY CONDITION TO THE SATISFACTION

ALL DRAWINGS TO BE READ IN CONJUNCTION WITH:

- VEGETATION MANAGEMENT AND TREE CLEARING REQUIREMENTS

OF THE SUPERINTENDENT AND RELEVANT COUNCIL REPRESENTATIVE.


PREPARED FOR LOWOOD ONE PTY LTD




GOLD COAST | BRISBANE | TOOWOOMBA **IPSWICH | MORETON BAY** PHONE: +61 7 5509 6400 FAX: +61 7 5509 6411 EMAIL: ADMIN@BURCHILLS.COM.AU COOTE BURCHILLS ENGINEERING PTY LTD ABN 76 166 942 365

DATE: 24-04-24 DRAWING No. VERSION: BE230128-01A

DESIGNS HAVE BEEN UNDERTAKEN USING SURVEY DATA PROVIDED BY ONE SURVEYORS DATED 6 NOVEMBER 2023





GENERAL EARTHWORKS NOTES:

- 1. ALL EARTHWORKS CONSTRUCTION UNDER THIS CONTRACT IS TO BE PERFORMED STRICTLY IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT PREPARED BY THE PRINCIPAL'S GEOTECHNICAL CONSULTANT.
- ALL COMPACTION TESTING UNDER THIS CONTRACT IS TO BE CARRIED OUT TO AS3798 LEVEL 1 STANDARD BY A NATA-ACCREDITED TESTING AUTHORITY. CERTIFICATION FOR ALL EARTHWORKS CONSTRUCTION AND TESTING IS TO BE PROVIDED BY A REGISTERED PROFESSIONAL ENGINEER QUEENSLAND (RPEQ) ENGAGED BY THE CONTRACTOR.
- 3. ALL DESIGN LEVELS SHOWN ON THE CONTRACT DRAWINGS ARE FINISHED SURFACE LEVELS FOLLOWING TOPSOIL REPLACEMENT.
- 4. ALL STRUCTURAL FILL MATERIAL PLACED SHALL BE COMPACTED TO THE FOLLOWING MINIMUM DENSITY IN ACCORDANCE WITH THE SPECIFICATION AND THE GEOTECHNICAL REPORT:
 - a) 95% DENSITY RATIO FOR GENERAL STRUCTURAL FILL (COHESIVE MATERIAL)
 b) 98% DENSITY RATIO FOR THE TOP 300mm DEPTH BELOW PAVEMENT SUBGRADE LEVEL (COHESIVE MATERIAL)
- 5. ALL EARTHWORKS BATTERS STEEPER THAN 1 IN 4 ARE TO BE LANDSCAPED IN ACCORDANCE WITH LANDSCAPE ARCHITECTS PLANS.
- EXISTING DAMS ARE TO BE DE-WATERED AND CLEANED-OUT. ALL UNSUITABLE OR SATURATED MATERIAL IS TO BE REMOVED AND REPLACED WITH SELECTED ON-SITE STRUCTURAL FILL MATERIAL AND COMPACTED AS SPECIFIED. FILLING OF DAMS IS TO BE COMPLETED UNDER LEVEL 1 BY GEOTECHNICAL ENGINEER.
- 7. PROVIDE CONDITION SURVEY OF ADJACENT RESIDENTIAL BUILDINGS FOR ALL PROPERTIES LOCATED WITHIN NOMINAL 100m OF EARTHWORKS OPERATIONS. CONDITION SURVEY TO BE UNDERTAKEN BY QUALIFIED PERSONNEL WITH BUILDING EXPERIENCE.


TYPICAL EARTHWORKS SEQUENCE NOTES:


- CONSTRUCT DIVERSION DRAINS AS DIRECTED TO DIVERT SITE RUNOFF AWAY FROM CONSTRUCTION AREAS. ESTABLISH DE-WATERING CONTROLS TO ENSURE THAT THE CONSTRUCTION AREAS REMAIN FREE OF SURFACE WATER AND PONDING.
- 2. FOLLOWING COMPLETION OF CLEARING OPERATIONS AND REMOVAL OF RESIDUAL VEGETATION AND DEBRIS, STRIP TOPSOIL TO A NOMINAL 150mm DEPTH AND PLACE IN TEMPORARY STOCKPILES IN LOCATIONS APPROVED BY THE SUPERINTENDENT.
- 3. PROOF-ROLL AND COMPACT THE PROPOSED FILL AREAS FOLLOWING TOPSOIL STRIPPING, TO THE SATISFACTION OF THE SUPERINTENDENT.
- 4. ANY STRIPPED AREAS WHICH DEMONSTRATE EXCESSIVE MOVEMENT OR DO NOT IMPROVE SUFFICIENTLY UNDER PROOF-ROLLING ARE TO BE REMOVED, REPLACED WITH APPROVED SITE MATERIAL AND COMPACTED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT.
- 5. ANY UNSUITABLE MATERIAL ENCOUNTERED, INCLUDING SILTY MATERIAL AND UN-CONTROLLED FILL IS TO BE EXCAVATED TO THE EXTENTS AND DEPTHS NOMINATED BY THE PRINCIPAL'S GEOTECHNICAL CONSULTANT, REMOVED TO NON-STRUCTURAL FILL AREAS OR TAKEN OFF-SITE AS DIRECTED AND REPLACED WITH APPROVED, COMPACTED FILL MATERIAL.
- PLACE STRUCTURAL FILL MATERIAL FROM SITE EXCAVATIONS TO NOMINATED SITE FILL AREAS, INCLUDING BENCHING AND COMPACTION IN ACCORDANCE WITH THE GEOTECHNICAL REPORT AND TRIMMING AND FINAL PROFILING OF BATTERS.
- 7. PROVIDE GRASSING TO TOPSOILED AREAS AS DIRECTED.

RETAINING WALL NOTES:

- 1. RETAINING WALLS, FOOTINGS, DRAINAGE, BACKFILL AND CONNECTION OF AGGREGATE DRAINS TO STORMWATER DRAINAGE SYSTEM TO BE DESIGNED AND CONSTRUCTED BY THE CONTRACTOR AND CERTIFIED BY AN SUITABLY QUALIFIED RPEQ
- 2. THESE DRAWINGS IDENTIFY SURFACE PROFILES, RETAINING WALL LOCATIONS, AND SETOUT INFORMATION ONLY. REFER TO CONTRACTOR SUPPLIED DRAWINGS FOR RPEQ STRUCTURAL DETAILS, WALL MATERIALS AND COMPACTION SPECIFICATIONS AND CONSTRUCTIBILITY INFORMATION.
- RETAINING WALL DESIGN ENGINEER TO PROVIDE RPEQ FORM 15 STRUCTURAL CERTIFICATE INCLUDING GEOTECHNICAL GLOBAL STABILITY CERTIFICATION BY GEOTECHNICAL ENGINEER. WALL DESIGN TO ASSUME SURCHARGE LOADING BEHIND WALL. DESIGN TO BE IN ACCORDANCE WITH AS4678 INCLUDING ALL REQUIRED DESIGN LOAD CASES AND COMBINATIONS.
- 4. RETAINING WALLS TO BE DESIGNED TO CONSIDER ALL LOADS INCLUDING CONSTRUCTION LOADS AND OPERATIONAL LOADS.
- 5. ANY GEOTECHINCAL INFORMATION PROVIDED BY THE PRINCIPAL OR THE SUPERINTENDENT SHALL BE FOR INFORMATION PURPOSES ONLY. THE CONTRACTOR AND THE RETAINING WALL DESIGN ENGINEER SHOULD SATISFY THEMSELVES OF THE DESIGN SOIL PARAMETERS AND UNDERTAKE AND ADDITIONAL GEOTECHNICAL INVESTIGATION DEEMED NECESSARY BY THE DESIGN ENGINEER.
- 6. THE CONTRACTOR SHALL ENSURE THAT ANY CONFLICT BETWEEN THESE PROJECT DRAWINGS AND THE RETAINING WALL DRAWINGS PREPARED BY THE RETAINING WALL DESIGN ENGINEER IS RESOLVED WITH THE SUPERINTENDENT PRIOR TO CONSTRUCTION COMMENCING.
- 7. A COPY OF THE RETAINING WALL DESIGN DRAWINGS, INCLUDING CONNECTION OF AGGREGATE DRAINS TO THE STORMWATER DRAINAGE SYSTEM, DESIGN PARAMETERS AND CERTIFICATION BE PROVIDED TO THE SUPERINTENDENT AT THE PRE-START MEETING PRIOR TO CONSTRUCTION COMMENCING.
- 8. ANY RETAINING WALL AND BATTER EXCEEDING THE HEIGHT OF 1.5m, THE CONTRACTOR SHALL UNDERTAKE A THIRD PARTY RPEQ REVIEW OF THE PROPOSED DESIGN.

NOTE:
RETAINING WALL DESIGN, CONSTRUCTION,
SUPERVISION AND CERTIFICATION TO BE
PROVIDED BY SPECIALIST SUB-CONTRACTOR.






PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD



COPYRIGHT (C)
This drawing is convigint and the property of Burchills

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only

be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba
Ipswich I Moreton Bay
Phone: +61 7 5509 6400
Fax: +61 7 5509 6411
Email: admin@burchills.com.au
Coote Burchills Engineering Pty Ltd
ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE

PRELIMINARY

NOT FOR CONSTRUCTION OR TENDER

EARTHWORKS NOTES AND DETAILS

DEVEL. APPLIC. No. :	-	DATE: 24-04-24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER :	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR ANI BURCHILLS ENGIN		S ABN 76 166 942 365

RPEQ No. :

DATUM : AHD FULL SIZE : A

PROJECT No.:


BE230128-01A

DATUM: AHD

FULL SIZE: A1

VERSION:

B B



PHASE 1 - SITE ESTABLISHMENT

- 1. ESTABLISH STABILISED ACCESS POINT, SITE OFFICES, AND PARKING AREAS (LOCATION TO BE CONFIRMED ON SITE).
- 2. DESIGNATE AND CORDON OFF ANY EXCLUSION AREAS (ANY AREAS OF THE SITE THAT ARE NOT TO BE ACCESSED).
- 3. INSTALL DUST FENCES ALONG ALL BOUNDARIES WITH EXISTING RESIDENTIAL DEVELOPMENT.
- 4. INSTALL SEDIMENT FENCES DOWNSLOPE FROM ALL DISTURBED AREAS AS INDICATED ON THE DRAWINGS (AS A MINIMUM).
- 5. INSTALL CLEAN WATER DIVERSION DRAINS WITH APPROPRIATE EROSION RESISTANT MATERIALS AND ROCK CHECK DAMS IN THE LOCATIONS INDICATED ON THE DRAWINGS.
- 6. CONSTRUCT TYPE B SEDIMENT BASINS PRIOR TO CARRYING OUT BROAD SCALE CLEARING IN THE SAME CATCHMENT.
- INSTALL ALL DIRTY WATER DIVERSIONS AND TEMPORARY SEDIMENT TRAPS ENSURING DE-WATERING FACILITIES ARE AVAILABLE WHEN REQUIRED.
- 8. COMMENCE CLEARING WORK STARTING AT THE TOP OF EACH CATCHMENT IDEALLY CLEARING SHOULD BE CARRIED OUT PROGRESSIVELY WITH THE BULK EARTHWORKS TO LIMIT EROSION.
- 9. PROGRESSIVELY STRIP, STOCKPILE, AND SEED TOPSOIL WITH A FAST GROWING PASTURE MIX. ALL TOPSOILS MUST BE CARED FOR DURING CONSTRUCTION TO ENSURE SUCCESSFUL REVEGETATION.
- 10. COMMENCE BULK EARTHWORKS, ENSURING A MINIMAL AMOUNT OF AREA IS DISTURBED AT ANY ONE TIME.


PHASE 2 - CLEARING AND BULK EARTHWORKS

- 11. RESPREAD TOPSOIL OVER COMPLETED EARTHWORKS AND SOW WITH SUITABLE VEGETATIVE COVER AS SOON AS PRACTICABLE.
- 12. ONCE ALL EXPOSED AREAS HAVE BEEN STABILISED WITH TOPSOIL AND AT LEAST 80% VEGETATIVE COVER, ALL TEMPORARY SEDIMENT CONTROLS INCLUDING SEDIMENT BASINS MAY BE REMOVED AND THE BULK EARTHWORKS IN THOSE AREAS COMPLETED AND REVEGETATED.
- 13. REMOVE ALL TEMPORARY CLEAN WATER DIVERSION DRAINS AND REVEGETATE.
- 14. REMOVE SITE OFFICES AND DUST FENCING AND REVEGETATE ANY OTHER DISTURBED AREAS.
- 15. ENSURE ALL EXTERNAL ROADS HAVE BEEN SWEPT CLEAN AND ARE FREE OF ANY SEDIMENT.

SEDIMENT AND EROSION CONTROL CERTIFICATION

I, TOBY BENNETT HEREBY CERTIFY THAT THE SEDIMENT AND EROSION CONTROL MEASURES AND DEVICES SHOWN ON THIS DRAWING HAVE BEEN DESIGNED IN ACCORDANCE WITH THE 'BEST PRACTICE EROSION AND SEDIMENT CONTROL' (IECA AUSTRALASIA, NOVEMBER 2008).

SIGNED RPEQ No. 21912 DATED 05-09-2023



SEDIMENT BASIN TYPE B TYPICAL SECTION

TEMPORARY SEDIMENT BASIN CALCULATIONS MIN. SEDIMENT | MIN. SEDIMENT APPROX. REQ APPROX. LENGTH APPROX. WIDTH APPROX. DEPTH TIME LAB FLOC 0.5Q1 CATCH L:W D_S TOTAL VOLUM **BATTER** CONC. SETTLE MINIMUM A_S (m²) ACTUAL V_S (m³) STORAGE AT SPILLWAY STORAGE VOLUM SED STORAGE AT SPILLWAY SETTLE RATE AT SPILLWAY BASIN ID (mm/hr) (m^3/s) AREA (ha) TYPE RATIO AT SPILLWAY (m) 1 in X (mins) DEPTH (m) DEPTH (m) (m/hr) DEPTH (m) (m) (m) (m) 0.37 7.336 0.6 29 0.109 0.40 0.60 1309 785 0.2 236 0.2 69.9 23.3 8.0 1020.7

PRELIMINARY
NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCIL RFI UPDATES	24-04-24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08-12-23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE

EROSION &
SEDIMENT CONTROL
BASIN NOTES AND
DETAILS

DEVEL. APPLIC. No.: -		DATE: 24-04-24
PROJECT LEADER: JO	NATHAN CUELL	
DESIGNER: TG		
DRAFTSPERSON: CD		
CHECKED: FR	ASER LUCAS	
APPROVED FOR AND C BURCHILLS ENGINEE		S ABN 76 166 942 365

RPEQ No. :

SCALE: AS NOTED

DATUM: AHD

FULL SIZE: A1

PROJECT No.:

DRAWING No.:

VERSION:

BE230128-01A

C251

B

EROSION AND SEDIMENT CONTROL NOTES


- 1. THIS DRAWING HAS BEEN PREPARED AS A GUIDE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MANAGE SITE SEDIMENT AND EROSION CONTROL MEASURES AND DURING THE CONSTRUCTION PERIOD INSTALL ADDITIONAL MEASURES WHERE SCOUR OR SEDIMENT TRANSPORT IS LIKELY TO OCCUP.
- 2. DELAY CLEARING, GRUBBING AND TOPSOIL STRIPPING UNTIL NECESSARY.
- 3. COMMENCE WORK ON SITE ONLY AFTER SEDIMENT AND EROSION CONTROL MEASURES ARE IN PLACE.
- 4. MANAGE SITE ENTRY/EXIT POINTS TO ENSURE SEDIMENT IS NOT TRACKED OFF SITE.
- SHAKEDOWN AREA: PROVIDES FOR CONSTRUCTION, SERVICE AND STAFF VEHICLES ENTERING PUBLIC ROADS. CONTRACTOR SHALL LOCATE TO SUIT SITE ACTIVITIES. CONSTRUCTED AS 250mm THICK LAYER OF COARSE (150mm -200mm) RIVER GRAVEL OVER A SINGLE LAYER OF HIGH STRENGTH GEOTEXTILE (15m x 5m).
- 6. THE CONTRACTOR SHALL INSTALL EITHER STORMWATER INLET SEDIMENT TRAPS OR EXCAVATED INLET ARRANGEMENT AT ALL STORMWATER STRUCTURES DURING THE CONSTRUCTION.
- 7. FILTER ROLLS SHALL BE INSTALLED AT GULLY PITS IMMEDIATELY AFTER GULLY PIT CONSTRUCTION AND LEFT IN PLACE DURING THE MAINTENANCE PERIOD. OPERATION OF ROLLS DURING PERIODS OF HEAVY RAIN TO BE MONITORED TO PREVENT FLOODING AND EROSION DAMAGE ELSEWHERE.
- 8. ARRANGE FOR EROSION CONTROL MEASURES TO BE INSTALLED AS CLOSE AS POSSIBLE TO THE SOURCE OF EROSION.
- 9. ENSURE STOCKPILED TOPSOIL AND EARTHWORKS ARE NOT ERODED BY WIND AND STORMWATER RUN-OFF AND ARE PROVIDED WITH A SEDIMENT FENCE AROUND THE LOW SIDE.
- 10. SEDIMENT FENCES HAVE BEEN ESTABLISHED UNDER BULK EARTHWORKS CONTRACT. ERECT SEDIMENT FENCES IF REQUIRED, GENERALLY ALONG THE LOW SIDE OF THE CONSTRUCTION SITE AND ALONG A LINE OF CONSTANT LEVEL. AS AN ALTERNATIVE TO BURYING THE SEDIMENT FENCE LOWER EDGE, THE CONTRACTOR MAY ELECT TO PLACE 200mm OF THE FABRIC ON THE GROUND UP-SLOPE OF THE FENCE AND COVER WITH 100mm MIN LAYER OF AGGREGATE.
- 11. TO PREVENT EROSION, TOPSOIL AND SEED IMMEDIATELY AFTER COMPLETION OF BULK EARTHWORKS TO FINISHED PROFILES.
- 12. PROVIDE TURF STRIP ADJACENT TO KERB FOR FULL LENGTH OF NEW ROAD AND TURF STRIP PLACED AT 90° TO KERB EVERY 10m FOR FULL WIDTH OF VERGE.
- 13. PRIOR TO COMPLETION OF CONSTRUCTION OF PAVEMENT AND SEALING, PLACE SANDBAGS AT 45° TO ARREST SCOUR AGAINST KERB AND CHANNEL AS FOLLOWS:

ROAD GRADE 0.5% - 5% - 25m MAX CRS.

5% - 10% - 10m MAX CRS. 10% - 15% - 15m MAX CRS.

15% - 20% - 5m MAX CRS.


- 14. SWEEP EXTERNAL ROADS WHERE SEDIMENT HAS BEEN DROPPED FROM CONSTRUCTION VEHICLES. DO NOT WASH SEDIMENT INTO THE STORMWATER SYSTEM.
- 15. ALL SEDIMENT AND EROSION CONTROL STRUCTURES, TRENCHES ETC. SHALL BE REGULARLY MAINTAINED AND INSPECTED FOR EFFECTIVENESS.
- 16. THE USE OF POTABLE WATER IS NOT PERMITTED IN SITE EARTHWORKS OPERATIONS, ROAD AND PAVEMENT CONSTRUCTION OR DUST SUPPRESSION. RECYCLED WATER IS REQUIRED TO BE USED AND IS TO BE IN ACCORDANCE WITH L.C.C GUIDELINES.



NOTE: SEDIMENT FENCE TO HAVE TURNOUTS AT 50m MAX INTERVALS.

NOTE

REFER TO IPWEAQ STANDARD DRAWINGS D-0040 AND D-0041 FOR ALL ADDITIONAL SEDIMENT CONTROL DETAILS




TYPICAL STOCKPILE CONFIGURATION


N.T.S.

NOTE:

 LOCATE STOCKPILES AT TOP OF CATCHMENT ON FLAT GROUND AND NOT WITHIN 5m OF CONCENTRATED FLOW PATHS.
 STOCKPILES SHOULD HAVE EARTHBANKS UPSLOPE FOR DIVERSION OF UPSTREAM WATER AROUND STOCKPILE AND SEDIMENT FENCES PLACED 1-2m DOWNSLOPE.





ROCK CHECK DAM TYPICAL CROSS SECTION
N.T.S.



DUST CONTROL FENCE

DUST CONTROL FENCE TO BE PLACED AS DIRECTED ON-SITE BY SUPERINTENDENT.





LONGITUDINAL SECTION

N.T.S.

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCIL RFI UPDATES	24-04-24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08-12-23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIME

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended. Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE

PRELIMINARY

NOT FOR CONSTRUCTION OR TENDER

EROSION &
SEDIMENT CONTROL
TYPICAL NOTES AND
DETAILS

DEVEL. APPLIC. No.: - DATE: 24-04-24

PROJECT LEADER: JONATHAN CUELL

DESIGNER: TG

DRAFTSPERSON: CD

CHECKED: FRASER LUCAS

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

IING SOLUTIONS ABN 76 166 942 3

SCALE: AS NOTED

PROJECT No.:

BE230128-01A

C252

BULL SIZE: A1

VERSION:

BE230128-01A

SEDIMENT AND EROSION CONTROL CERTIFICATION

I HEREBY CERTIFY THAT THE SEDIMENT AND EROSION CONTROL MEASURES AND DEVICES SHOWN ON THIS DRAWING HAVE BEEN DESIGNED IN ACCORDANCE WITH THE 'BEST PRACTICE EROSION AND SEDIMENT CONTROL' (IECA AUSTRALASIA, NOVEMBER 2008).

SIGNED PPEQ No. DATED

NOTE:

REFER TO IPWEAQ STANDARD DRAWINGS D-0040 AND D-0041 FOR ALL ADDITIONAL SEDIMENT CONTROL DETAILS.

364

				& OPPORTUNITIES GN – NORMAL DES			
Design Element	Associated risks & opportunities	Raw risk assessment		Raw risk rating	Treatment Measures to avoid, minimize or treat the risk.	Responsibility	Residual risk rating
		Like od	Con seq uen ce				
CONSTRUCTION PHASE							
SITE ACCESS	Unsafe site access and egress point, restricted access, flooding, unauthorised access from persons or animals	L	M	L-M	Prepare site specific Construction Traffic Management Plan and Workplace Health and Safety Management Plan	Principal Contractor	L
CLEARING & DEMOLITION	Removal of existing structures, decommision of services, vegetation clearing and fauna management	М	Н	М-Н	Contractor to obtain Demolition Permit, arrange all service disconnections with asset ownerand carry out vegetation works in accordance with Vegetation and Fauna Management Plan	Principal Contractor	L
EXISTING SERVICES	Distrub or damage existing services and infrastructure, overhead powerlines, work adjacent to existing services, existing service relocations	M	Н	М-Н	Client to commission detailed site survey and service potholing at critical locations. Contractor to undertake Dial Before You Dig and service verification with service authoritiy providers and undertake additional potholing prior to construction	Client and Principal Contractor	L-M
EXCAVATION & TRENCHING	Unstable existing slopes and landslip, steep cut profiles, deep trench excavations, working at heights, intercept water table, dispersive soils, acid sulphate soils	M	Н	М-Н	Client to commission a geotechnical investigation and contractors to undertake own investigations. Temporary and final earthworks profiles confirmed by client's geotechnical consultant. Tempory earthworks profile to be confirmed by Contractor's geotechnical consultant. Contractor to provide temporary benching, fencing, stabilisation and shoring.	Client and Principal Contractor	L
MATERIALS HANDLING	Manual handling, handling and disposal of sharps, repeative work processeds, hazardous substances	Н	М	М-Н	Contractor or provide a site specific Workplace Health and Safety Management Plan including Material Safety Data Sheets	Principal Contractor	L
PLANT & EQUIPMENT	Operation of plant and machinery, site access by visitors, material deliveries and waste removal	М	Н	М-Н	Contractor or provide a site specific Workplace Health and Safety Management Plan including register of operator machinery tickets. Contractor to maintain a site visitor register and provide site specific induction to all visitors	Principal Contractor	L
OPERATIONAL PHASE							
ROADS & PATHWAYS	General road safety, flood free access, pedestrian and cyclist injuries, inadequate signage	L	Н	М	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
STORWATER / FLOODING	Hazard from storm and flood water depths and velocities, ponding and access to inlets, outlets and basins	М	Н	М-Н	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
WATER & SEWER	Blockages, contamination, interuption to service, access to fittings, confined space access	L	M	L-M	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
WALLS & FENCING	Risk of falls, unauthoried access from persons and animals, structural failure	M	М	М	Design, approvals and construction undertaken in accordance with Australian, State Government and Local Authority standards, codes, guidelines and best practice	Asset Owner	L
MAINTENANCE PHASE							
ROADS & PATHWAYS	All as for construction and operation phases					Asset Owner	
STORWATER / FLOODING	All as for construction and operation phases					Asset Owner	
WATER & SEWER	All as for construction and operation phases					Asset Owner	
WALLS & FENCING	All as for construction and operation phases					Asset Owner	
REFURBISHMENT PHASE							
ROADS & PATHWAYS	All as for construction and operation phases					Asset Owner	
STORWATER / FLOODING	All as for construction and operation phases					Asset Owner	
WATER & SEWER	All as for construction and operation phases					Asset Owner	
WALLS & FENCING	All as for construction and operation phases					Asset Owner	
DEMOLITION PHASE							
ROADS & PATHWAYS	All as for construction and operation phases					Asset Owner	
STORWATER / FLOODING	All as for construction and operation phases					Asset Owner	
WATER & SEWER	All as for construction and operation phases					Asset Owner	
WALLS & FENCING	All as for construction and operation phases					Asset Owner	

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

ORIGINAL SIZE BEFORE REDUCTION COUNCIL RFI UPDATES 24-04-24 PRELIMINARY CIVIL ENGINEERING DESIGN 08-12-23 VER. DESCRIPTION DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:

EARTHWORKS OPW - STAGE 1

DRAWING TITLE:

HAZARD RISK REGISTER -**DESIGN RISKS**

DEVEL. APPLIC. No.: -DATE: 24-04-24 PROJECT LEADER: JONATHAN CUELL DESIGNER: DRAFTSPERSON: CD FRASER LUCAS CHECKED: APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

DATUM : AHD SCALE: AS NOTED FULL SIZE : A1 PROJECT No.: DRAWING No.: VERSION: BE230128-01A C900

The experience **you deserve** \geqslant



Our Ref: BE230128-TM-HIA-Stg1-02.docx

Enquiries: Melissa Blum

TECHNICAL MEMORANDUM

Date	26/04/2024
То	Lowood One Pty Ltd
From	Melissa Blum
Project	BE230128 – 2983 Forest Hill Fernvale Road, Lowood
Subject	Hydraulic Impact Assessment – Stage 1

1. BACKGROUND

Lowood One Pty Ltd have engaged Burchills Engineering Solutions to prepare a Hydraulic Impact Assessment (HIA) to accompany a Development Application to be submitted to Somerset Regional Council (the 'Council' or 'SRC'). The Application sought is a Reconfiguring a Lot Approval for Stage 1 of the development which includes 48 lots, including 4 duplex allotments.

The properties included in this Development Application include:

- Lot 56 Forest Hill Fernvale Road, Lowood (Lot 56 on SP 197415); and
- Lot 57 Forest Hill Fernvale Road, Lowood (Lot 57 on SP 197415).

This report has been prepared to address the requirements of the Somerset Region Planning Scheme, Version 4.2 (2016), specifically the Flood Hazard Overlay Code. It should be read in conjunction with the Conceptual Stormwater Management Plan (CSMP) for Stage 1 (BE230128-MEM-CSMP-Stg1-02.pdf) and HIA contained within the Master Stormwater Management Plan (MSMP) for the Masterplan (BE230128-RP-MSPM-02.pdf).

2. SITE DETAILS

The subject site is located at 2983 Forest Hill Fernvale Road, Lowood, QLD and can be formally described as Lot 56 and 57 SP 197415 with a total area of 41.68ha. Refer to Figure 2.1 for the site locality.



Figure 2.1 Site Locality (QLD Globe, 2023)

2.1 Proposed Development

The proposed Stage 1 development includes 48 lots, including 4 duplex allotments, as shown in Figure 2.2. These lots will be filled above the Design Flood Level (1% AEP plus 300mm freeboard). The proposed Regional Detention Basin associated with the masterplan development is not proposed in Stage 1 works and the impact this has on flooding is outlined in Section 4 of this Memorandum.



The experience you deserve



Figure 2.2 Proposed Stage 1 Development (Burchills, 2024)

3. HYDRAULIC MODEL

Burchills have utilised Councils Lowood Flood Study (Water Technology, 2019) TUFLOW model for this assessment. The Lowood model represents the Lowood local catchment, draining into the Brisbane River to the north, the model does not include Brisbane River flooding. The model covers an area of 17km² and uses a 3m grid resolution. The resolution of the model is considered fit-for-purpose for the hydraulic impact assessment (HIA).

The model used for this assessment was developed as part of the Masterplan assessment, full details of the model changes and validation are presented in the Masterplan HIA report (BE230128-RP-HIA-Masterplan-02.docx). The following sections relate to changes to the Masterplan Model.

3.1 Post-Development Scenario Representation

The post-development topography was represented in the model through the design DEM, as indicated within Appendix B, and included the fill pads, basins and channel.

In addition to this, a bund has been included along the northern boundary, with $3 \times 2.1 \text{m} \times 0.6 \text{m}$ culverts controlling the outflow from the Site.

3.1.1 Post-Development Hydrology

The hydrology for the post-development scenario was also updated to reflect the impervious area changes associated with Stage 1 only. This was achieved by using an XP-SWMM model to represent the Site, using eight sub catchments. The catchment parameters for the modified catchments are presented in Table 3.1.

Table 3.1 Catchment Modification & Representation

Catchments	Area	Fraction Imp. (%)
P04	1.1	5
P05	0.8	5
P06	13.5	75



4. RESULTS

4.1 Pre-Development Flood Behaviour

The area of Stage 1 begins to get inundated from the 0.5EY, with ponding to the east of the channel, close to Forest Hill Fernvale Road. In the 0.2EY event, there is an addition of a breakout flow to the west of the channel, near the northern boundary of the Stage. These two areas of inundation get deeper and cover a larger extent with the larger events.

Generally in the existing Scenario flood waters are contained to existing waterways and there is only minor flood within the floodplain of depth less than 300mm.

4.2 Post-Development Flood Behaviour

In the post-developed scenario the flood is conveyed through the primary site drainage channel to the undeveloped portion of the site where it joins on to the existing waterway before reaching the LPD. It is important to note that the proposed regional detention basin associated with the masterplan development is not proposed during Stage 1 works. Flood waters are contained within the Stage 1 channel and the development lots achieve the required freeboard.

Flood depth within the channel is generally less than 1.5m in depth for the 1% AEP event. In more frequent events such as the 0.5EY, the flood depth in the channel ranges from 0.2-0.5m.

Flood velocity in the channel is relatively slow, peaking at approximately 1.5m/s in the 2% and 1% AEP events. The flow velocities within the channel are in accordance with QUDM (2017), Section 9.5.3 – 'Recommended maximum average velocities'.

Flow hazard within the channel is greater than 0.6m²/s and is not safe for pedestrian access.

Peak water surface level, depth, velocity, hazard and afflux plots for the modelled events have been included in Appendix D of this report.

4.3 Flood Impacts

Flood afflux occurs due to a lack of stormwater controls at the development, with the proposed Regional Detention Basin not coming online until future stages of the development. It is important to note that once the development is realised in its entirety, flood impacts are reduced.

The proposed development results in an increase in flood level downstream of the development. Flood afflux is at its highest in the 1% AEP flood event, with flood level generally increasing by 10-30mm downstream and peak afflux of up to 50mm occurring in an existing downstream dam. More frequent flood events such as the 39% AEP event result in an improvement in flood impact downstream of the development.

An assessment of Stage 1's impact of flood velocity was also completed, with flood velocity change limited to a few select areas in the downstream floodplain. The small increase in flood velocity (less than 0.2m/s) is not likely to give rise to additional scour potential and is considered acceptable.

It is important to note that no flood afflux occurs on any existing structures / dwellings and is wholly contained to land uses associated with agricultural purposes.





5. CONCLUSION

This HIA for Stage 1 has been prepared for Lowood One Pty Ltd to accompany the Development Application to allow for the development of 48 lots, including 4 duplex allotments on 2983 Forest Hill Fernvale Road, Lowood.

This HIA builds on the assessment and findings from the Masterplan assessment (BE23128-RP-MSMP-02) and assess the proposed Stage 1 development in isolation from the controls proposed by the Masterplan development. The results of the assessment indicate that flood waters can be appropriately conveyed through the development in accordance with the relevant guidelines.

The findings of the HIA indicate that changes to flood levels downstream occur, with impacts occurring on undeveloped agricultural land only and no significant impacts on any existing structures / dwellings. The proposed development will not cause additional scour potential downstream.

Yours sincerely,

Melissa Blum

Senior Water Engineer

Samuel Huddy

Senior Water Engineer RPEQ - 29555






Appendix A – Proposed Plans of Development







Prepared for: LOWOOD ONE PTY LTD

Designer: TG
Checked: CD
Date: 24.03.24

STAGE 1 - SUBDIVISION LAYOUT
CONCEPT CIVIL DRAWINGS

SCALE 15 0 15 30 45 60 75 (metres)
1: 1500 (FULL SIZE)

BE230128-01-SK010-B



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Englineering Pty Ltd ABN 76 166 942 365




Appendix B – Burchills Civil Engineering Drawings



PROPOSED LAND SUBDIVISION AT 2983 FOREST HILL FERNVALE RD, LOWOOD QUEENSLAND 4311

CONCEPT CIVIL ENGINEERING STAGE 1

CONTRACT BE230128-01



DRAWING INDEX				
DWG No.	DESCRIPTION			
SK000	COVER SHEET			
SK200	BULK EARTHWORKS LAYOUT PLAN			
SK201	EARTHWORKS SECTIONS			
SK300	ROADWORKS AND DRAINAGE LAYOUT PLAN			
SK301	TYPICAL ROAD CROSS SECTIONS			
SK310	ROAD 1 LONGITUDINAL SECTIONS			
SK311	ROADS 4 & 5 LONGITUDINAL SECTIONS			
SK312	ROADS 6 & 7 LONGITUDINAL SECTIONS			
SK313	ROAD 8 LONGITUDINAL SECTIONS			
SK320	BIO-RETENTION BASIN DETAIL PLAN			
SK321	BIO-RETENTION BASIN DETAILS			
SK350	INTERSECTION FUNCTION LAYOUT PLAN			
SK500	CONCEPT WATER AND SEWER LAYOUT PLAN			

PREPARED FOR


LOWOOD ONE PTY LTD




GOLD COAST | BRISBANE | TOOWOOMBA
IPSWICH | MORETON BAY
PHONE: +61 7 5509 6400
FAX: +61 7 5509 6411
EMAIL: ADMIN@BURCHILLS.COM.AU
COOTE BURCHILLS ENGINEERING PTY LTD
ABN 76 166 942 365

DATE: 24.04.24

PROJECT No.: DRAWING No. : VERSION: BE230128-01 SK000 B






PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

LOWOOD ONE PTY LTD



This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.




CONCEPT CIVIL ENGINEERING


EARTHWORKS SECTIONS


DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER :	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AN	D ON BEHALF OF	

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

DATUM : AHD DRAWING No.: VERSION: SK201







PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

A 1 ORIGINAL SIZE BEFORE REDUCTION		
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE:


TYPICAL ROAD **CROSS SECTIONS**

	DEVEL. APPLIC. No. :	-	DATE: 24.04.24
	PROJECT LEADER :	JONATHAN CUELL	
	DESIGNER:	TG	
	DRAFTSPERSON:	CD	
	CHECKED:	FRASER LUCAS	
	APPROVED FOR AN	D ON BEHALF OF	

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

PRELIMINARY NOT FOR CONSTRUCTION OR TENDER

SCALE: AS NOTED DATUM : AHD PROJECT No.: DRAWING No.: VERSION: BE230128-01 SK301



PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE:

ROAD 1 LONGITUDINAL SECTIONS

DEVEL. APPLIC. No. :	-	DATE: 24.04.24
PROJECT LEADER :	JONATHAN CUELL	
DESIGNER:	TG	
DRAFTSPERSON:	CD	
CHECKED:	FRASER LUCAS	
APPROVED FOR AN	D ON BEHALE OF	

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

SCALE: AS NOTED DATUM : AHD PROJECT No.: DRAWING No.: VERSION: BE230128-01 SK310

PRELIMINARY NOT FOR CONSTRUCTION OR TENDER


VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres) (FULL SIZE)

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD



COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER
This drawing and its con

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROADS 4 & 5 LONGITUDINAL SECTIONS

	DEVEL. APPLIC. No. :	-	DATE: 24.04.24
	PROJECT LEADER :	JONATHAN CUELL	
	DESIGNER :	TG	
	DRAFTSPERSON:	CD	
	CHECKED:	FRASER LUCAS	
	APPROVED FOR AND ON BEHALF OF		

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

RPEQ No. :

PROJECT No.:

BE230128-01


DATUM: AHD

FULL SIZE: A1

VERSION:

BK311

B



HORIZONTAL GEOMETRY

-0.6%

15mVC R = 625

-1.25

58.299

59.55 59.49

58 58

SAG TP (

20mVC R = 1666.67

0.24 0.13 0.12 0.15

57.610 57.581 57.580 57.610 57.663

57.37 57.44 57.45 57.49 57.52 0.44

EXISTING SURFACE \(\square\)

VERTICAL GRADE (%)

DATUM RL 51.0

LEVEL

LEVEL

VERTICAL CURVE LENGTH (m)

VERTICAL CURVE RADIUS (m)

DEPTH OF CUT (-ve)

HEIGHT OF FILL (+ve)

FINISHED SURFACE

EXISTING SURFACE

CONTROL LINE

CHAINAGE

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)

ROAD 4 LONGITUDINAL SECTION

ROAD 5 LONGITUDINAL SECTION

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

PRELIMINARY

NOT FOR CONSTRUCTION OR TENDER

EXISTING SURFACE ~ SAG L DESIGN SURFACE TO STATE 1.3\$5% VERTICAL GRADE (%) 15mVC R = 346.02 15mVC R = 900.88 VERTICAL CURVE LENGTH (m) VERTICAL CURVE RADIUS (m) DATUM RL 49.0 DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve) FINISHED SURFACE 55.235 55.057 55.450 55.453 55.776 55.932 55.971 54.921 54.932 LEVEL EXISTING SURFACE 56.15 56.15 56.15 56.15 56.15 LEVEL 56. CONTROL LINE CHAINAGE


HORIZONTAL GEOMETRY

ROAD 6 LONGITUDINAL SECTION

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)



HORIZONTAL GEOMETRY

HORIZONTAL GEOMETRY

ROAD 7 LONGITUDINAL SECTION

VERTICAL SCALE 1 0 1 2 3 4 5 1:100 (metres)

HORIZONTAL SCALE 10 0 10 20 30 40 50 1:1000 (metres)

(FULL SIZE)

PRELIMINARY
NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	A 1 ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROADS 6 & 7 LONGITUDINAL SECTIONS

	DEVEL. APPLIC. No. :	-	DATE: 24.04.24
	PROJECT LEADER :	JONATHAN CUELL	
	DESIGNER:	TG	
	DRAFTSPERSON:	CD	
	CHECKED:	FRASER LUCAS	
	APPROVED FOR AN	D ON BEHALF OF	

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

DDEO N

SCALE: AS NOTED

PROJECT No.:

BE230128-01

DATUM: AHD

FULL SIZE: A1

VERSION:

BK312

B

┌ DESIGN SURFACE 1 IN 4 TEMPORARY BATTER -1 IN 4 TEMPORARY BATTER FUTURE SURFACE \ - CULVERT GROUP 2 7x2100x600 RCBCs -0.6% 0.633% VERTICAL GRADE (%) $= \frac{30 \text{mVC}}{\text{R} = 2433.1}$ VERTICAL CURVE LENGTH (m) 30mVCR = 2481.71 VERTICAL CURVE RADIUS (m) DATUM RL 47.0 DEPTH OF CUT (-ve) HEIGHT OF FILL (+ve) 0.41 FINISHED SURFACE 54.923 54.941 54.976 54.428 LEVEL EXISTING SURFACE 54.42 54.41 54.77 54.81 54.01 54.45 54.35 53.68 LEVEL 54.9 54. 53 22, 22, CONTROL LINE 291.815 CHAINAGE

ROAD 8 LONGITUDINAL SECTION

VERTICAL SCALE 2 0 2 4 6 8 10 1:200 (meters)

HORIZONTAL SCALE 20 0 20 40 60 80 100 1:2000 (meters) (FULL SIZE)

HORIZONTAL GEOMETRY

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

B COUNCILL RFI UPDATES 24.04.24
A PRELIMINARY CIVIL ENGINEERING DESIGN 08.12.23
VER. DESCRIPTION DATE

COPYRIGHT C

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

DISCLAIMER

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

NOTE
This is an unc

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.

Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au Coote Burchills Engineering Pty Ltd ABN 76 166 942 365

PROJECT:

CONCEPT CIVIL ENGINEERING

DRAWING TITLE :

ROAD 8 LONGITUDINAL SECTIONS

DEVEL. APPLIC. No.: - DATE: 24.04.24

PROJECT LEADER: JONATHAN CUELL

DESIGNER: TG

DRAFTSPERSON: CD

CHECKED: FRASER LUCAS

APPROVED FOR AND ON BEHALF OF BURCHILLS ENGINEERING SOLUTIONS ABN 76 166 942 365

RPEQ No. :

PRELIMINARY

NOT FOR CONSTRUCTION OR TENDER

SCALE: AS NOTED

DATUM: AHD

FULL SIZE: A1


PROJECT No.:


DRAWING No.:

VERSION:


SK313

B









INTERSECTION FUNCTION LAYOUT PLAN

5 0 5 10 15 20 25 (metres) 1:500 (FULL SIZE)

LEGEND

	DEVELOPMENT SITE BOUNDARY
	PROPOSED LOT BOUNDARY
	PROPOSED ROAD CONTROL LINE
W	EXISTING Ø150 WATER MAIN
RM	EXISTING SEWER RISING MAIN
s	EXISTING SEWER MAIN
C	EXISTING COMMS
——————————————————————————————————————	EXISTING OVERHEAD ELECTRIC
>>	EXISTING FLOWPATH / WATERWAY

PRELIMINARY NOT FOR CONSTRUCTION OR TENDER

PROPOSED LAND DEVELOPMENT

2983 FOREST HILL FERNVALE RD, LOWOOD QLD 4311

FOR LOWOOD ONE PTY LTD

	ORIGINAL SIZE BEFORE REDUCTION	
В	COUNCILL RFI UPDATES	24.04.24
Α	PRELIMINARY CIVIL ENGINEERING DESIGN	08.12.23
VER.	DESCRIPTION	DATE

COPYRIGHT (C)

This drawing is copyright and the property of Burchills Engineering Solutions. It must not be retained, copied or used without the authority of Burchills Engineering Solutions.

This drawing and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended.

Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the drawing for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party.

This is an uncontrolled document issued for information purposes only, unless the checked sections are signed or completed.
Figured dimensions take precedence over scale. Do not scale reduced size drawings. Verify dimensions prior to commencing any on-site or off-site works or fabrication.



Gold Coast I Brisbane I Toowoomba Ipswich I Moreton Bay Phone: +61 7 5509 6400 Fax: +61 7 5509 6411 Email: admin@burchills.com.au

Coote Burchills Engineering Pty Ltd

ABN 76 166 942 365

PROJECT:


CONCEPT CIVIL ENGINEERING

DRAWING TITLE:

INTERSECTION FUNCTION LAYOUT PLAN

	DEVEL. APPLIC. No. :	-	DATE: 24.04.24
	PROJECT LEADER :	JONATHAN CUELL	
	DESIGNER :	TG	
	DRAFTSPERSON:	CD	
	CHECKED:	FRASER LUCAS	
	APPROVED FOR AN BURCHILLS ENGIN		S ABN 76 166 942 365


SCALE: AS NOTED DATUM : AHD PROJECT No.: DRAWING No.: VERSION: BE230128-01 SK350






Appendix C – Flood Modelling Results





This figure and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended. Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the figure for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party. Some or all of the data presented on this plan may have been digitised or sourced from third parties, and as such may contain spatial innaccuracies.



This figure and its contents are electronically generated, are confidential and may only be used for the purpose for which they were intended. Burchills Engineering Solutions will not accept responsibility for any consequences arising from the use of the figure for other than its intended purpose or where the drawing has been altered, amended or changed either manually or electronically by any third party. Some or all of the data presented on this plan may have been digitised or sourced from third parties, and as such may contain spatial innaccuracies.

